

LOCATION		78000200	78000400	78000500	78000600	78000650	78000100	78000310	78008340	78100100			78100105	78100200	78300100	78300200
		THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER			RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	STATION	(FT)	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(FT)	(FT)	ONE-WAY AMBER	ONE-WAY CRYSTAL	TWO-WAY AMBER	(EACH)	(EACH)	(SQ FT)	(EACH)
US 30																
KANE																
1234+00	1249+00	5,662	0	0	108	0	23	0	0	0	21	17	0	110	36	147
1249+00	1261+00	2,094	0	2,618	267	0	0	0	0	0	101	0	0	120	952	221
1261+00	1275+00	1,327	0	1,232	125	0	0	750	1,501	0	30	0	30	164	1,191	224
1275+00	1277+13/1278+21	0	0	223	0	0	0	504	223	0	18	0	0	0	314	18
KENDALL																
1277+13/1278+21	1281+00	0	0	0	0	0	0	340	216	0	16	0	0	0	184	16
IL 31																
KENDALL																
79+00	92+00	2,408	410	260	67	146	109	0	0	0	23	1	0	0	291	24
92+00	100+00	1,802	220	0	0	0	73	0	0	0	18	0	0	0	73	18
100+00	106+11/107+36	2,024	343	296	185	48	182	0	0	0	16	3	0	50	288	69
KANE																
106+11/107+36	111+00	1,169	300	160	351	81	73	0	0	0	8	0	0	53	294	61
111+00	124+00	3,157	605	0	403	90	73	0	0	0	28	0	0	151	362	179
124+00	138+00	1,136	370	0	0	0	109	0	0	0	33	0	0	58	122	91
138+00	140+70	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
RAMP A																
300+00	315+00	2,591	0	0	0	0	0	0	0	0	0	0	0	3	0	3
315+00	317+80	0	0	0	0	0	0	0	0	0	0	0	0	3	0	3
RAMP B																
400+00	413+34	2,110	849	0	0	51	270	0	0	6	3	0	0	3	297	12
RAMP C																
500+00	509+54	2,378	0	0	0	0	0	0	0	0	0	0	0	4	0	4
RAMP D																
600+00	611+65	1,527	247	0	0	37	125	0	0	6	4	0	0	4	94	14
KANE		23,150	2,371	4,233	1,254	259	673	1,254	1,724	12	245	17	30	673	3,661	976
KENDALL		6,234	973	556	252	194	364	340	216	0	73	5	0	50	835	127
TOTALS		29,384	3,344	4,789	1,506	453	1,037	1,595	1,940	12	317	21	30	723	4,497	1,103

P:\Jobs\2010\20100303\cd\sthe\00\0160133-sht-Schedule-PMK.dgn
 6/15/2012 3:44:50 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 6/15/2012	DATE - 06/15/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31
PAVEMENT MARKING SCHEDULE**

SCALE: N.T.S. SHEET NO. 1 OF 1

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	50
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				