

STAGE 1

LOCATION		X7030030 WET REE TEM TP T3 4	70300220 TEMPORARY PAVEMENT MARKING LINE 4	70300240 TEMPORARY PAVEMENT MARKING LINE 6	70300250 TEMPORARY PAVEMENT MARKING LINE 8	70300260 TEMPORARY PAVEMENT MARKING LINE 12	70300280 TEMPORARY PAVEMENT MARKING LINE 24	78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	70300210 TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS
STATION	STATION	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	EACH	(SQ FT)
US 30									
1237+66	1249+00	0	4158	0	0	0	0	50	0
1249+00	1261+00	0	4500	265	0	0	0	60	0
1261+00	1275+00	0	4546	0	0	55	30	72	36
1275+00	1280+00	885	1500	0	0	0	0	0	0
IL 31									
80+00	92+00	0	1810	0	0	0	0	0	0
92+00	100+00	0	700	0	0	0	0	0	0
100+00	111+00	0	2035	0	0	0	0	0	0
111+00	124+00	0	1819	306	0	0	0	0	73
124+00	138+00	0	0	0	0	0	0	0	0
138+00	140+00	0	0	0	0	0	0	0	0
RAMPS A, B, C, D		0	970	0	102	125	12	17	36
TOTALS		885	22038	571	102	180	42	200	146

STAGE 2

LOCATION		X7030030 WET REE TEM TP T3 4	70300220 TEMPORARY PAVEMENT MARKING LINE 4	70300240 TEMPORARY PAVEMENT MARKING LINE 6	70300250 TEMPORARY PAVEMENT MARKING LINE 8	70300260 TEMPORARY PAVEMENT MARKING LINE 12	70300280 TEMPORARY PAVEMENT MARKING LINE 24	78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	70300210 TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS
STATION	STATION	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	EACH	(SQ FT)
US 30									
1237+66	1249+00	0	3328	0	0	0	0	57	0
1249+00	1261+00	0	2400	0	0	0	0	60	0
1261+00	1275+00	0	4557	158	0	55	30	77	36
1275+00	1280+00	886	1528	0	0	0	0	0	0
IL 31									
80+00	92+00	0	0	0	0	0	0	0	0
92+00	100+00	0	0	0	0	0	0	0	0
100+00	111+00	0	0	0	0	0	0	0	0
111+00	124+00	0	0	0	0	0	0	0	0
124+00	138+00	0	0	0	0	0	0	0	0
138+00	140+00	0	0	0	0	0	0	0	0
RAMPS A, B, C, D		0	1366	165	0	140	12	0	36
TOTALS		886	13179	323	0	195	42	193	73

H:\Jobs\2010\20100303\CAD\1\stre\dgn\00\0160133-sht+Schedule-MOT.dgn 8/8/2012 2:50:35 PM

USER NAME = 1654	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RS	REVISED -
PLOT DATE = 8/8/2012	DATE - 06/15/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**U.S. ROUTE 30 AT IL ROUTE 31
MAINTENANCE OF TRAFFIC SCHEDULES**

SCALE: N.T.S. SHEET NO. 1 OF 6

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11 VB) R-3	*	507	51
* KANE AND KENDALL			CONTRACT NO. 60133	
ILLINOIS FED. AID PROJECT				