



BILL OF MATERIAL

Item	Unit	Quantity
Concrete Removal	cu. yd.	10.0
Epoxy Crack Injection	ft.	9.0
Anchor Bolts, 3/4"	each	1

LEGEND

- Concrete Removal
- Epoxy Crack Injection
- Hairline Crack, no repair required

NOTES:

1. Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.

P:\1052200\20103003\cad\structural\dgn\045-0039_find\00\1060133-e058-e-abut-rep.dgn
 6/14/2012 6:08:28 PM

USER NAME =	DESIGNED - J.Z. 6/15/2012	REVISED -
	CHECKED - J.A.Z. 6/15/2012	REVISED -
PLOT SCALE =	DRAWN - E.E.J. 6/15/2012	REVISED -
PLOT DATE =	CHECKED - J.J.G. 6/15/2012	REVISED -

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11VB) R-3	KANE	507	279
CONTRACT NO. 60133			ILLINOIS FED. AID PROJECT	