



**NOTES:**

1. Cost of anchor rods, nuts and washers for light poles and conduit is included with Concrete Superstructure. See Electrical Plans for details and payment of other electrical components.
2. Anchor Rods for Light Poles shall be ASTM F1554, Grade 105 and shall be fully hot dip galvanized.
3. Electrical conduit in parapet shall have a minimum clearance of 1/2" from reinforcement bars.

P:\1052200\20103003\cadd\structural\dgn\retwall\_final\00\160133-sa06-1r.dgn  
 6/14/2012 6:09:22 PM

**GRÄEF**  
 8501 W. Higgins Road, Suite 280  
 Chicago, Illinois 60631; (773) 399-0112

USER NAME =	DESIGNED - R.K.-Z. . 6/15/2012	REVISED -
	CHECKED - J.Z. 6/15/2012	REVISED -
PLOT SCALE =	DRAWN - R.K.-Z. . 6/15/2012	REVISED -
PLOT DATE =	CHECKED - J.J.G. 6/15/2012	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**RETAINING WALL STRUCTURAL LIGHTING**  
**STRUCTURE NUMBER 045-W014**

SHEET NO. SA6 OF 11 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	(10 & 11VB) R-3	KANE	507	343
STA. 1252+00.00			CONTRACT NO. 60133	

ILLINOIS FED. AID PROJECT