

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021	
				XXX FEDERAL XXX STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XXX FEDERAL XXX STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XXX FEDERAL XXX STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XXX FEDERAL XXX STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY	XXX FEDERAL XXX STATE	
40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10"	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SO YD	3488	3488																		
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SO YD	8661	8661																		
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42001300	PROTECTIVE COAT	SO YD		SEE TABLE 1 ALTERNATE QUANTITIES																		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	344		92																252	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	2031		1882																109	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	104054	96249	375	2243	994															
42400800	DETECTABLE WARNINGS	SO FT	1193	1117			60															
44000100	PAVEMENT REMOVAL	SO YD	86160	82460			3700															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	216	216																		
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	7411	7087			284															
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	22042	20801			1241															
44000600	SIDEWALK REMOVAL	SO FT	62600	56117			2290															
44003100	MEDIAN REMOVAL	SO FT	25667	19751			5916															
44004250	PAVED SHOULDER REMOVAL	SO YD	2400	2400																		
44201821	CLASS D PATCHES, TYPE IV, 14"	SO YD	1030	1030																		
48101202	AGGREGATE SHOULDERS, TYPE B	CU YD	510	510																		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	453	453																		
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SO YD	1739	1739																		
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SO YD	25	25																		
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SO YD	1834	1834																		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1																		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1																		
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1																		
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1																		
550A0050	STORM SEWERS, CLASS A, TYPE I 12"	FOOT	4145	4145																		
550A0070	STORM SEWERS, CLASS A, TYPE I 15"	FOOT	928	928																		
550A0090	STORM SEWERS, CLASS A, TYPE I 18"	FOOT	272	272																		
550A0110	STORM SEWERS, CLASS A, TYPE I 21"	FOOT	225	225																		
550A0120	STORM SEWERS, CLASS A, TYPE I 24"	FOOT	1152	1152																		
550A0140	STORM SEWERS, CLASS A, TYPE I 30"	FOOT	425	425																		
550A0160	STORM SEWERS, CLASS A, TYPE I 36"	FOOT	3744	3744																		

Rev.