

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL PART 1	ROADWAY RECONSTRUCTION 0004				LIGHTING 0021					SIGNING 0021		UTILITIES 0043		TRAFFIC SIGNALS 0021				INTER-CONNECT 0021			
				XX% FEDERAL XX% STATE	100% DIXMOOR	100% HARVEY	100% COOK COUNTY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% DIXMOOR	100% HARVEY	100% POSEN	XX% FEDERAL XX% STATE	100% COOK COUNTY	100% POSEN	100% HARVEY	XX% FEDERAL XX% STATE	100% MIDLOTHIAN	100% POSEN	100% HARVEY		XX% FEDERAL XX% STATE		
				70300520	PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	251803	251803																
70300540	PAVEMENT MARKING TAPE, TYPE III, 6 INCH	FOOT	20141	20141																				
70300550	PAVEMENT MARKING TAPE, TYPE III, 8 INCH	FOOT	2980	2980																				
70300560	PAVEMENT MARKING TAPE, TYPE III, 12 INCH	FOOT	2566	2566																				
70300570	PAVEMENT MARKING TAPE, TYPE III, 24 INCH	FOOT	5333	5333																				
X8250060	TEMPORARY LIGHTING CONTROLLER	EACH	1					0.57	0.10				0.33											
X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1					0.57	0.08				0.35											
X8350012	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	10					10																
X8360215	LIGHTPOLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	45					27					18											
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1																1					
X8730255	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	127																					127
X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	619	619																				
X8800025	SIGNAL HEAD .LED, 1#FACE, 3#SECTION, SPAN WIRE MOUNTED	EACH	12																12					
X8850102	INDUCTION LOOP	FOOT	100	100																				
X8900015	TEMPORARY TRAFFIC SIGNAL INTERCONNECTION SYSTEM	L SUM	1																					1
X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	2					1		1														
X8950205	REBUILD EXISTING HANDHOLE, SPECIAL	EACH	1	1																				
XX000679	OUT AND CAP EXISTING WATER MAIN	EACH	22																					
89501420	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, COMPLETE	EACH	7																2	3	2			
XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	11700											11700										
XX003435	PGC DRIVEWAY REMOVAL AND REPLACEMENT	50 YD	40																					
56400825	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	8											7	1									
XX006500	SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT	FOOT	42																					
X5611112	DUCTILE IRON WATER MAIN, CLASS 52, WITH POLYETHYLENE ENCASEMENT, 12"	FOOT	3251											3251										
X5611108	DUCTILE IRON WATER MAIN, CLASS 52, WITH POLYETHYLENE ENCASEMENT, 8"	FOOT	892											892										
XX008154	RELOCATE EXISTING RADIO INTERCONNECT SYSTEM	EACH	2																					2
XX008156	LINE STOP 10"	EACH	1											1										
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																				
Z0016702	DETOUR SIGNING	L SUM	1	1																				
Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	15554	15171																				383
Z0023206	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	77770	75855																				1915
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2																				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3																				
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4																				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2																				
Z0030850	TEMPORARY INFORMATION SIGNING	50 FT	781	781																				

TYLIN INTERNATIONAL

DESIGNED - EMK	REVISED -
DRAWN - EMK	REVISED -
CHECKED - SES	REVISED -
DATE - 5/23/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

147TH STREET PROJECT
SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 10 OF 11 SHEETS STA. TO STA.

F.A.I. RTE. XX	SECTION 10405-1 & 0506-2) R-1	COUNTY COOK	TOTAL SHEETS 577	SHEET NO. 13
CONTRACT NO. 60M57				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

P:\60254057-2949\road\p10.147\txp10_500_SHT10.dgn
 10:53:32 AM
 7/3/2012
 Rev.