

147TH STREET PROJECT DRIVEWAY SCHEDULE

ALIGNMENT	STATION	OFFSET	TYPE	WIDTH (FT)	LENGTH FROM FACE OF CURB TO ROW LINE (FT)	CURB LENGTH (FT)	P.C.C. DRIVEWAY PAVEMENT, 8" (SQ YD)	P.C.C. DRIVEWAY PAVEMENT, 6" (SQ YD)
147TH STREET	1005+73.65	LEFT	C.E.	14.6	2.1		3	
147TH STREET	1007+68.95	LEFT	C.E.	24.0	14.0		44	
147th STREET	1008+16.97	LEFT	C.E.	24.0	14.0		44	
147th STREET	1010+62.76	LEFT	C.E.	30.0	14.0	29	48	
147th STREET	1011+15.45	LEFT	C.E.	24.0	14.4	30	40	
147th STREET	1011+60.45	LEFT	C.E.	12.0	15.5	37	23	
147th STREET	1012+08.37	LEFT	P.E.	25.0	16.0			50
147th STREET	1013+89.79	LEFT	C.E.	35.0	16.0	33	64	
147th STREET	1014+61.66	LEFT	C.E.	35.0	16.0	33	64	
147th STREET	1014+95.36	RIGHT	C.E.	33.0	16.0	33	60	
147th STREET	1015+04.34	LEFT	P.E.	10.0	16.0			23
147th STREET	1030+99.93	RIGHT	C.E.	30.0	11.0		41	
147th STREET	1031+21.62	LEFT	C.E.	22.8	11.0		33	
147th STREET	1034+05.92	RIGHT	C.E.	28.0	11.0		38	
147th STREET	1034+76.68	RIGHT	P.E.	10.0	11.0			18
147th STREET	1037+16.50	RIGHT	C.E.	32.0	11.0		43	
147th STREET	1037+42.35	LEFT	C.E.	24.0	11.0		34	
147th STREET	1037+80.56	RIGHT	C.E.	32.0	11.0		43	
147th STREET	1038+38.30	LEFT	C.E.	35.0	11.0		47	
147th STREET	1038+38.45	RIGHT	C.E.	32.0	11.0		43	
147th STREET	1039+14.43	RIGHT	C.E.	28.0	11.0		38	
147th STREET	1039+14.43	LEFT	C.E.	30.0	11.0		41	
147th ST (CLEVELAND)	1039+57.46	77.82' RT	C.E.	24.0	14.1		44	
147th ST (CLEVELAND)	1039+60.42	79.18' LT	C.E.	35.0	15.8	32	62	
147th STREET	1072+23.86	RIGHT	C.E.	25.0	13.0	27	38	
147th STREET	1073+02.49	LEFT	C.E.	36.0	10.0	21	41	
147th STREET	1077+94.29	RIGHT	C.E.	24.0	8.1	18	21	
147th STREET	1078+78.64	LEFT	C.E.	35.0	7.6		32	
147th STREET	1078+82.71	RIGHT	C.E.	24.0	8.1	19	21	
DIXIE/WESTERN	5999+49.22	RIGHT	C.E.	35.0	13.1		58	
DIXIE/WESTERN (148TH PL)	6001+73.87	61.68' RT	C.E.	24.0	23.9	48	69	
DIXIE/WESTERN	6002+87.05	RIGHT	C.E.	30.0	13.7		54	
DIXIE/WESTERN	6007+76.70	RIGHT	C.E.	35.0	11.9		51	
DIXIE/WESTERN	6008+90.00	RIGHT	C.E.	14.0	12.2		26	
DIXIE/WESTERN	6009+67.07	LEFT	C.E.	24.0	26.0	62	89	
DIXIE/WESTERN	6014+03.07	LEFT	C.E.	35.0	12.0	39	45	
DIXIE/WESTERN	6014+46.33	RIGHT	C.E.	35.0	12.0		53	
DIXIE/WESTERN	6019+27.90	RIGHT	C.E.	20.0	35.7	74	80	
DIXIE/WESTERN	6020+16.86	RIGHT	C.E.	20.0	35.6	74	79	
DIXIE/WESTERN	6021+52.18	LEFT	C.E.	30.0	11.5		44	
DIXIE/WESTERN	6023+13.10	LEFT	C.E.	30.0	11.5		44	
DIXIE/WESTERN	6023+93.35	LEFT	C.E.	22.8	11.5		35	
DIXIE/WESTERN	6025+93.52	LEFT	C.E.	35.0	11.4		47	
KEDZIE AVE	5012+91.95	RIGHT	C.E.	32.0	16.0	32	57	
KEDZIE AVE	5013+35.72	LEFT	C.E.	30.0	14.5	32	50	
KEDZIE AVE	5013+43.95	RIGHT	C.E.	32.0	16.0	35	59	
KEDZIE AVE	5013+76.44	LEFT	C.E.	12.0	16.0	35	24	
KEDZIE AVE	5014+39.54	LEFT	P.E.	12.0	14.5			24
KEDZIE AVE	5014+93.75	LEFT	P.E.	12.0	14.5			24
KEDZIE AVE	5015+40.98	LEFT	P.E.	9.0	14.5			19
KEDZIE AVE	5015+88.13	RIGHT	P.E.	14.0	11.0			23
KEDZIE AVE	5016+23.96	LEFT	P.E.	24.0	15.2			45
KEDZIE AVE	5016+75.18	LEFT	P.E.	12.0	16.7			25
KEDZIE AVE	5016+94.93	LEFT	P.E.	14.4	17.3			30
KEDZIE AVE	5017+07.02	RIGHT	P.E.	14.0	13.6			29
TOTAL						743	2011	309

	USER NAME =	DESIGNED - DPS	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>147TH STREET PROJECT</b> <b>DRIVEWAY SCHEDULE</b>		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - DPS	REVISED -				XX	(0405-1 & 0506-2) R-1	COOK	577	35
	PLOT DATE =	CHECKED -	REVISED -				CONTRACT NO. 60M57		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		
DATE - 5/23/2012				SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.					