

LOCATION				STORM SEWER REMOVALS								STORM SEWER TO BE FILLED WITH CLSM (CU YD)	TRENCH BACKFILL (CU YD)	CATCH BASIN TO BE ADJ W/ NEW TYPE 8 GRATE (EACH)	CATCH BASIN TO BE ADJ W/ NEW TYPE 11 F & G (EACH)	MANHOLES TO BE ADJ W/ NEW TYPE 1 F & CL LID (EACH)	INLETS TO BE ADJ W/ NEW TYPE 11 F & G (EACH)	INLETS TO BE ADJ W/ NEW TYPE 24 F & G (EACH)	INLETS TO BE RECON W/ NEW TYPE 24 F & G (EACH)	VALVE VAULTS TO BE ADJ W/ NEW TYPE 1 F & CL LID (EACH)	REMOVING				
UPSTREAM STATION	DOWNSTREAM STATION	OFFSET (FOOT)	RT	6" (FOOT)	8" (FOOT)	10" (FOOT)	12" (FOOT)	15" (FOOT)	18" (FOOT)	24" (FOOT)	30" (FOOT)										36" (FOOT)	MANHOLES (EACH)	CATCH BASINS (EACH)	INLETS (EACH)	
	1071+93.9	59.4	RT												1										
	1072+11.9	57.5	RT											1											
	1072+34.6	10.7	LT																	1					
1072+34.6	1072+45.3		LT/RT				19							23.0								1			
	1072+35.8	38.5	LT																						
1072+35.8	1072+34.6		LT										0.8												
	1072+59	8.2	LT																	1					
1072+59	1072+34.6		LT				25						41	9.5											
	1072+45.3		RT											88.5											
	1072+85.6	3.6	RT										55	119.1						1					
1072+85.6	1072+86.5		RT																						
	1073+03.3	58.4	LT												1										
	1073+05.1	47	RT																			1			
1073+05.1	1073+04.6		RT				12							3.8											
	1073+60.5	46.1	RT																			1			
1073+60.5	1073+67.3		RT				15							14.0											
	1073+67.3	59.5	RT												1										
	1074+01.9	56.9	RT												1										
	1074+42.5	8.2	LT												1										
	1074+64.1	6.8	RT																1						
	1075+33.9	34.7	LT																		1				
	1075+73.5	3.8	RT												1										
	1076+38.1	43.8	LT																		1				
1076+38.1	1076+55.8		LT										0.7												
	1076+40.7	39	LT											2.0								1			
1076+40.7	1077+12.9		LT																						
	1076+41.5	47.3	LT												1										
	1076+77.4	91.9	RT												1										
1077+40.9	1076+77.4		RT											2.2											
	1077+12.9	28.8	LT																		1				
1077+12.9	1077+81.6		LT											2.0											
	1077+40.9	48	RT																	1					
1077+99.5	1077+40.9		RT											1.2											
	1077+81.6	27.6	LT											0.9							1				
1077+81.6	1078+11.3		LT																						
	1077+99.5	32.2	RT																			1			
	1078+11.3	28.4	LT																		1				
	1078+47.8	31	LT																	1					
	1079+22.5	26.7	LT																			1			
	1079+28.7	40.4	RT																			1			
1079+28.7	1079+52.4		RT																						
	1079+51.2	43.2	LT												1										
	1079+52.4	40.4	RT												1										
	1079+73.9	40.2	RT													1									
	1079+89.8	15.4	LT																1						
	1079+97.2	25.8	LT													1									
SUBTOTAL 147TH STREET				7	24	43	1524	495	74	10	231	106	481.2	877.5	0	3	17	2	2	0	3	28	55	30	
RAMP E																									
	4114+48.6	111.6	RT																				1		
4114+48.6	4114+84.1		RT											1.9											
	4114+47.8	25.8	LT																			1			
4114+47.8	4114+89.2		LT										42	48.4											
4115+07.4	4115+27.8		RT/LT											1.6											
	4115+27.8	9	LT																			1			
4115+27.8	4115+67.2		LT											2.4											
SUBTOTAL RAMP E				0	0	0	0	0	42	0	0	0	5.9	48.4	0	0	0	0	0	0	0	0	3	0	
RAMP F1																									
4200+93.9	4200+97.9		LT				20							5.1											
	4200+97.9	12.9	LT																			1			
4200+97.9	4200+52.3		LT/RT											1.4											
	4201+01.5	18.5	LT																				1		
4201+01.5	4200+97.9		LT				6							2.4											
	4201+13.3	113.8	RT																			1			
4201+13.3	4200+52.3		RT				125							20.2											
SUBTOTAL RAMP F1				0	0	0	151	0	0	0	0	0	1.4	27.7	0	0	0	0	0	0	0	1	2	0	
RAMP J																									
4310+88.9	4310+88.9	37.4	LT																				1		
4310+88.9	4311+54.3		LT											2.0											



USER NAME -	DESIGNED - JRS	REVISED - JRS 12/01/2011
	DRAWN - MJF	REVISED - JRS 02/15/2012
PLOT SCALE -	CHECKED - APS	REVISED - JRS 05/04/2012
PLOT DATE	DATE - 7/22/2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>147TH STREET PROJECT</b>			
<b>EXISTING DRAINAGE REMOVAL AND ADJUSTMENT SCHEDULE</b>			
SCALE: N/A	SHEET NO. 4 OF 6 SHEETS	STA. TO STA.	

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(0405-1 & 0506-2) R-1	COOK	577	252
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60M57	