LOCATION				STORM SEWER REMOVALS									STORM SEWER TO BE FILLED WITH CLSM	TRENCH BACKFILL	CATCH BASIN TO BE ADJ W/ NEW TYPE 8 GRATE	CATCH BASIN TO BE ADJ W/ NEW TYPE 11 F & G	MANHOLES TO BE ADJ W/ NEW TYPE 1 F & CL LID	INLETS TO BE ADJ W/ NEW TYPE 11 F & G	INLETS TO BE ADJ W/ NEW TYPE 24 F & G	INLETS TO BE RECON W/ NEW TYPE 24 F & G	VALVE VAULTS TO BE ADJ W/ NEW TYPE 1 F & CL LID	REMOVING		
UPSTREAM STATION	DOWNSTREAM STATION	OFFSET (FOOT)		6" (FOOT)	8" (FOOT)	10" (FOOT)	12" (FOOT)	15" (FOOT)	18" (FOOT)	24" (FOOT)	30" (FOOT)	36" (FOOT)	(CU YD)	(CU YD)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	MANHOLES (EACH)	CATCH BASINS (EACH)	INLETS (EACH)
	4310+99.1	103.6	RT												1									
	4311+54.3	16.2	LT																					1
4311+54.3	4311+80.5		LT/RT				61																	
SUBTOTAL RAMP J				0	0	0	61	0	0	0	0	0	2.0	0.0	1	0	0	0	0	0	0	0	1	1
RAMP K																								
	4401+01.5	33.5	LT																				1	
4401+64.4	4401+01.5		LT					70																
	4401+64.4	40.5	LT																				1	
	4401+68.9	88.2	RT												1									
SUBTOTAL RAMP K				0	0	0	0	70	0	0	0	0	0.0	0.0	1	0	0	0	0	0	0	0	2	0
KEDZIE AVENUE																								
	5013+04.2	38.2	RT														1							
	5013+09.7	6.7	RT														1							
	5013+09.8	32.2	LT																1					
	5013+14.4	32.3	RT																1					
	5013+69.5	41.2	RT														1							
	5014+73.5	32.2	RT																	1				
	5014+74.6	32	LT																1					
	5014+74.9	0.8	LT														1							
	5016+37.1	31.3	RT																1					
	5016+41.2	0	LT														1							
	5016+42	31	LT																1					
	5017+87.4	40.1	LT												1									
	5017+89.6	27.8	RT																1					
	5018+53.5	53.8	LT																1					
	5018+83.9	53.2	LT																1					
	5018+89	39.6	LT														1							
	5018+93.6	25.9	LT														1							
	5018+99	17.8	RT														1							
	5019+14.4	24.5	LT														1							
SUBTOTAL KEDZIE AVENUE				0	0	0	0	0	0	0	0	0	0.0	0.0	1	0	9	0	8	1	0	0	0	0
WESTERN AV / DIXIE HWY																								
	6001+87.5	33.7	RT													1								
	6004+87.5	46.7	RT																				1	
6004+87.5	6005+07.5		RT		18									2.7										
	6005+07.5	48.7	RT														1							
	6005+10.2	45.7	LT														1							
	6005+25	33.1	RT																			1		
6005+25	6005+07.5		RT	21										4.0										
	6005+31	36.3	RT																				1	
6005+31	6005+25		RT	7										0.6										
	6005+98.7	24.6	RT														1							
6007+17.6	6008+72.2		LT										4.5											
	6007+31.4	22.7	RT																					1
6007+31.4	6008+74.5		RT				143																	
	6007+48.3	34.3	RT														1							
	6008+72.2	29.4	LT																					1
6008+72.2	6009+15.6		LT										1.4											
	6008+74.5	26.8	RT																					1
6008+74.5	6009+55		RT				81							24.2										
6009+15.6	6010+29.8		LT										3.3											
	6009+16.1	47.7	LT														1							
	6009+54	29.9	LT																					1
6009+54	6009+15.6		LT										1.2											
	6009+55	31.5	RT																				1	
6009+55	6009+55.8		RT				9							3.0										
	6009+55.8	41.2	RT																				1	
6009+55.8	6009+71.1		RT				34							7.9										
	6010+29.8	49.2	LT																				1	
6010+13.8	6010+35.9		RT	24										3.1										
	6010+35.9	39.8	RT																				1	
6010+35.9	6010+29.5		RT				29							5.4										
	6010+36.9	29.8	LT																					1
6010+36.9	6010+39.1		LT				16							2.9										
6010+29.8	6010+96.1		LT										3.0											
	6010+86.3	87.9	RT														1							
	6010+96.1	46.9	LT														1							
	6010+99.3	74.5	RT														1							

P10_SCH_DRREM_SHT05_HRGREEN.dgn

HRGreen.com
Illinois Professional Design Firm # 184-001322

USER NAME =	DESIGNED - JRS	REVISED - JRS 12/01/2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN - MJF	REVISED - JRS 02/15/2012	
PLOT SCALE =	CHECKED - APS	REVISED - JRS 05/04/2012	
PLOT DATE =	DATE - 7/22/2011	REVISED -	

147TH STREET PROJECT

EXISTING DRAINAGE REMOVAL AND ADJUSTMENT SCHEDULE

SCALE: N/A | SHEET NO. 5 OF 6 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(0405-1 & 0506-2) R-1	COOK	577	253
		CONTRACT NO. 60M57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

4/26/2012 11:18:39 AM