

SIGN NO.	ALIGNMENT							SUPPORT INFORMATION					SIGN DESCRIPTION	
		PROP. STATION	OFFSET	TYPE	WIDTH (FT)	HEIGHT (FT)	AREA (FT)	TYPE	POST QUANTITY	POST LENGTH (FT)	TELES. STEEL POSTS (EACH)	BASE FOR TELES. STEEL (EACH)		GROUND OR PAVEMENT MOUNT
213	147th ST	SAME AS ABOVE		1	2	2.0	4.0							D9-2
214	147th ST	SAME AS ABOVE		1	1.75	1.3	2.2							M6-1L
215	147th ST	1077+99.91	5.96 RT	1	2.5	3.0	7.5	METAL	1	10.0	1	1	PAVEMENT	R3-5L
216	147th ST	1078+58.32	39.24 RT	1	2.5	3.0	7.5	LIGHT POLE						R2-1
217	147th ST	1079+87.81	48.19 RT	1	2.5	2.5	6.3	METAL	1	10.8	1	1	PAVEMENT	R1-1
218	147th ST	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
219	147th ST	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
220	147th ST	1079+35.47	50.44 LT	1	2.5	2.5	6.3	METAL	1	15.8	1		GROUND	R1-1
221	147th ST	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
222	147th ST	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
223	147th ST	5998+47.34	55.88LT	2	4	2.5	10.0	METAL	1	14.5	1		GROUND	R11-2
224	147th ST	6013+08.74	7.72 RT	1	2.5	2.5	6.3	METAL	1	9.5	1	1	PAVEMENT	R3-8
225	DIXIE/WESTERN	SAME AS ABOVE		1	2	2.5	5.0							R4-7
226	DIXIE/WESTERN	6013+52.71	60.90 LT	1	2	2.0	4.0	LIGHT POLE						M1-1100
227	DIXIE/WESTERN	SAME AS ABOVE		1	1.75	1.3	2.2							M6-4
228	DIXIE/WESTERN	6014+73.46	60.84 LT	1	2	1.0	2.0	LIGHT POLE						M4-5
229	DIXIE/WESTERN	SAME AS ABOVE		1	2	2.0	4.0							M1-1
230	DIXIE/WESTERN	SAME AS ABOVE		1	1.75	1.3	2.2							M6-1R
231	DIXIE/WESTERN	6010+61.84	48.95 RT	1	2	2.0	4.0	METAL	1	10.3	1	1	PAVEMENT	M1-1100
232	DIXIE/WESTERN	SAME AS ABOVE		1	1.75	1.3	2.2							M6-4
233	DIXIE/WESTERN	6011+13.67	13.77 LT	1	2	2.5	5.0	METAL	1	9.5	1	1	PAVEMENT	R4-7
234	DIXIE/WESTERN	SAME AS ABOVE		1	2.5	2.5	6.3							R3-8
235	DIXIE/WESTERN	5998+91.03	33.23 LT	1	1	1.5	1.5	METAL	1	14.0	1		GROUND	R7-1
236	DIXIE/WESTERN	SAME AS ABOVE		1	1	0.5	0.5							R7-201aP
237	DIXIE/WESTERN	6001+85.95	43.61 RT	1	2.5	2.5	6.3	METAL	1	15.8	1		GROUND	R1-1
238	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
239	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
240	DIXIE/WESTERN	6002+91.83	38.40 LT	1	1	1.5	1.5	METAL	1	14.0	1		GROUND	R7-1
241	DIXIE/WESTERN	SAME AS ABOVE		1	1	0.5	0.5							R7-201aP
242	DIXIE/WESTERN	6003+86.57	36.45 RT	1	2.5	3.0	7.5	METAL	1	11.5	1	1	PAVEMENT	R2-1
243	DIXIE/WESTERN	SAME AS ABOVE		1	1	1.5	1.5							R7-1
244	DIXIE/WESTERN	6004+91.70	62.09 LT	1	2.5	2.5	6.3	METAL	1	15.8	1		GROUND	R1-1
245	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
246	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
247	DIXIE/WESTERN	6005+32.95	70.22 LT	1	2	2.5	5.0	METAL	1	14.5	1		GROUND	R4-7
248	DIXIE/WESTERN	6005+30.61	54.90 RT	1	2.5	2.5	6.3	METAL	1	15.8	1		GROUND	R1-1
249	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
250	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
251	DIXIE/WESTERN	6005+67.00	1.83 RT	1	2	2.5	5.0	METAL	1	9.5	1	1	PAVEMENT	R4-7
252	DIXIE/WESTERN	SAME AS ABOVE		1	2	2.5	5.0							R3-5L
253	DIXIE/WESTERN	6008+24.28	46.30 RT	1	2.5	3.0	7.5	METAL	1	10.0	1	1	PAVEMENT	R3-5R
254	DIXIE/WESTERN	6008+64.58	14.04 LT	1	2.5	2.5	6.3	METAL	1	9.5	1	1	PAVEMENT	R3-8
255	DIXIE/WESTERN	6007+38.51	41.50 RT	1	2	1.0	2.0	METAL	1	16.3	1		GROUND	M4-5
256	DIXIE/WESTERN	SAME AS ABOVE		1	2	2.0	4.0							M1-1
257	DIXIE/WESTERN	SAME AS ABOVE		1	1.75	1.3	2.2							M6-1L
258	DIXIE/WESTERN	6009+48.47	70.08 LT	1	2.5	2.5	6.3	METAL	1	14.5	1		GROUND	R1-1
259	DIXIE/WESTERN	6015+44.96	52.60 RT	1	2.5	2.5	6.3	METAL	1	15.8	1		GROUND	R1-1
260	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
261	DIXIE/WESTERN	SAME AS ABOVE		1	1.25	0.7	0.8							D3-1
262	DIXIE/WESTERN	6015+73.69	54.59 LT	1	2.5	3.0	7.5	METAL	1	10.0	1	1	PAVEMENT	R3-5R
263	DIXIE/WESTERN	6019+60.44	43.66 RT	1	3	3.0	9.0	METAL	1	18.0	1		GROUND	R5-1
264	DIXIE/WESTERN	SAME AS ABOVE		1	3	3.0	9.0							R3-2
265	DIXIE/WESTERN	6020+32.56	37.50 LT	1	3	3.0	9.0	METAL	1	13.0	1	1	PAVEMENT	R3-2

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - BES	REVISED -
PLOT SCALE =	DRAWN - BES	REVISED -
PLOT DATE =	CHECKED - JPM	REVISED -
	DATE - 5/23/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**147TH STREET PROJECT
PROPOSED SIGN SCHEDULE**

SCALE: 1" = 50' SHEET NO. 5 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
XX	(0405-1 & 0506-2) R-1	COOK	577	344B
FED. ROAD DIST. NO.			CONTRACT NO. 60M57	
ILLINOIS			FED. AID PROJECT	

p:\602540(57-294)\road\p10_147th\PI0_SCHED_PRSIGN_SHT01.dgn 3:52:24 PM 6/20/2012