

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 0044						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
20800150	TRENCH BACKFILL	CU YD	2.4	2.4															
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NSO	TON	1	1															
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	16	16															
44000100	PAVEMENT REMOVAL	SQ YD	34	34															
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	16	16															
44213204	TIE BARS 3/4"	EACH	22	22															
50300225	CONCRETE STRUCTURES	CU YD	21	21															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1															
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	44	44															
XX197300	SLOTTED DRAIN	FOOT	75	75															
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2															
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4															
Z0056604	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	13	13															