## **ABBREVIATIONS**

@ - AT A.B. - ANCHOR BOLT A/C - AIR CONDITIONING ACT - ACOUSTICAL TILE AD. - AREA DRAIN, AS SHOWN ADJ. - ADJUST - ADJUSTABLE A.F.F. - ABOVE FLOOR FINISH AL - ALUM - ALUMINUM ALT. - ALTERNATE

AP. - ACCESS PANEL APPROX - APPROXIMATELY BB. - BULLETIN BOARD B.C. - BRICK COURSES RD BOARD BITUM. - BITUMINOUS BLDG. - BUILDING BLK - BLOCK, BLKG. - BLOCKING BM., B.M. - BEAM, BENCH MARK B.O.F. - BOTTOM OF FOOTING BOT. - BOTTOM B.P. - BASE PLATE - CENTERLINE

CAB. - CABINET CAP. CAPACITY C.B. - CHALK BOARD C.C. - CENTER TO CENTER C.D. - CEILING DIFFUSER CER. - CERAMIC C.F.M. - CUBIC FEET PER MINUTE C.H. - COAT HOOK C.J. - CONTROL JOINT CLR. - CLEAR, COLOR CLG. - CEILING CLKG. - CAULKING C-CLOSET C.M.U. - CONCRETE MASONRY UNITS C.O. - CLEANOUT COL. - COLUMN CONC. - CONCRETE CONST. - CONSTRUCTION CONT. - CONTINUOUS

CONTR. - CONTRACT COR. BD. - CORNER BEAD C.R. - COLD ROLLED CPT. - CARPET C.T. - CERAMIC TILE CTSK - COUNTERSUNK C.W. - COLD WATER C.F./C.L - CONTRACTOR FURNISHED/

DR. - DOOR D.S. - DOWNSPOUT

D.W. - DISHWASHER

DBL. - DOUBLE

FXH . FXHAUST

EXIST. - EXISTING

EXT. - EXTERIOR

ELEC. - ELECTRICAL

FOLIR - FOLIPMENT

E.W. - EACH WAY

F.A. - FRESH AIR

F.A.P. - FIRE ALARM PANEL F.C. - FURRED CEILING

FDN., FOUND. - FOUNDATION F.E.C. - FIRE EXTINGUISHER CABINET

F.F.EL - FINISH FLOOR ELEVATION

F.H. - FIRE HYDRANT, FLAT HEAD

F.H.C. - FIRE HOSE CABINET

FT. - FOOT, FEET, FT. - SQ. FT. F.T.D. - FACIAL TISSUE DISPENSER

F.C.U. - FAN COIL UNIT F.D. - FLOOR DRAIN, FIRE DAMPER

F.G. - FINISH GRADE

FIN. - FINISH (ED) (ES)

FL - FLOOR

FTG. - FOOTING

EQ. - EQUAL

E. - EAST EA - EACH

EXP. - EXPANSION, EXPOSED

E.J., EXP. JT. - EXPANSION JOINT EL - ELEVATION

DIA - DIAMETER DET. - DETAIL DIA - DIAMETER DIAG - DIAGONAL DIAGRAM DIM - DIMENSION DISP - DISPENSES D.L - DEAD LOAD

DN. - DOWN D.P. - DAMPPROOFING, DUMPSTER PAD, DEPTH D.W.C. - DRINKING WATER COOLER E.W.C. - ELECTRIC WATER COOLER E.W.H. - ELECTRIC WATER HEATER

HWY. - HIGHWAY I.D. - INSIDE DIAMETER IN, - INCH INSUL - INSULATION INT. - INTERIOR INV - INVERT

E.F.S. - EXTERIOR INSULATION FINISH SYSTEM E.F. - EACH FACE JAN. - JANITORS'S CLOSET JT. - JOINT JST. - JOIST J.C. - JANITOR'S CLOSET K.O. - KNOCKOUT K.P.-KICK PLATE K.D.-KILN DRIED

FURN. - FURNITURE

GALV. - GALVANIZED

G.F./C.I. - GOVERNMENT FURNISHED/ CONTRACTOR INSTALLED

GL, G.L. - GLASS, GRADE LINE GR. - GRADE

GWB - GYPSUM WALL BOARD

GYP. BD. - GYPSUM BOARD

G.F.E. - GOVERNMENT FURNISHED - EQUIPMENT

G.B. - GRAB BARS

GRD. - GROUND G.T. - GREASE TRAP

H., HGT., HT. - HEIGHT

H.B. - HOSE BIBB H.M. - HOLLOW METAL

HORIZ - HORIZONTAL

H.P. - HIGH POINT

HR - HOUR HTG - HEATING

H.W. - HOT WATER HDW. - HARDWARE

FUT. - FUTURE

GAL - GALLON

GA - GAGE

LAB, - LABORATORY LAV. - LAVATORY LB. - POUND LBS. - POUNDS LG. - LONG LH. - LEFT HAND LKR. - LOCKER LL - LIVE LOAD LLHALONG LEG HORIZONTAL

L.L.V. - LONG LEG VERTICAL L.P. - LOW POINT

MAINT, - MAINTENANCE MAS - MASCINEY MAX. - MAXIMUM M.C. - MEDICINE CABINET MECH - MECHANICAL

MEZZ. - MEZZANINE MET, - METAL MFG - MANUFACTURER M.G. - MIRROR GLASS MH - MANHOLF G.F.R.C. - GLASS FIBER REINFORCED CONCRETE MIN. - MINIMUM MISC - MISCELLANEOUS M.O. - MASONRY OPENINGS

MULL - MULLION N. - NORTH N.LC. - NOT IN CONTRACT NO NUMBER N.T.S. - NOT TO SCALE

O.C. - ON CENTER (S)
O.D. - OUTSIDE DIAMETER, OVERFLOW DRAIN OFF, - OFFICE O.H. - OPPOSITE HAND O.J. - OPEN JOISTED OPP. - OPPOSITE O.R. - OUTSIDE RADIUS OZ. - OUNCES

O.A - OUTSIDE AIR

P.E.J. - PREMOLDED EXP. JT. MAT. P.I. - POINT OF INTERSECTION P.J.F. - PREFORMED JOINT FILLER PL.-PLATE PLAS.-PLASTER P. LAM. - PLASTIC LAMINATE PLYWD. - PLYWOOD PNL - PANEL PNLS. - PANELS PR. - PAIR
P.S.F. - POUNDS PER SQUARE FOOT P.S.I. - POUNDS PER SQUARE INCH PT. - POINT, POINT OF TANGENT P.T.D. - PAPER TOWEL DISPENSER

OTY - QUANTITY R.B. - RESILIENT BASE R. - RADIUS, RISER R.A. - RETURN AIR RAD. - RADIUS

Q.T. - QUARRY TILE

R.D. - ROOF DRAIN VEST, · VESTIBULE RECP. - RECEPTACLE REF. - REFERENCE V.F. - VINYL FABRIC V.S. - VENT STACK V.T.R. - VENT THROUGH ROOF V.W.C. - VINYL WALL COVERING REINF, - REINFORCE (D), (MENT) REQ'D. - REQUIRED RET. - RETAINING REV. - REVISION WI-WITH RM(S) - ROOM(S) W/O-WITHOUT

WAINS - WAINSCOT

W.D. - WOOD

WDW - WINDOW

WT. - WEIGHT WTR. - WATER

W.G. - WIRE GLASS

W.C. - WATER CLOSET

W.R. - WASTE RECEPTACLE

W.W.F. - WELDED WIRE FABRIC

W.P. - WATERPROOF, WEATHERPROOF

R.O. - ROUGH OPENING SAN. - SANITARY S.B. - SPLASH BLOCK S.C. - SOLIO CORE, SHOWER CURTAIN SCHED. - SCHEDULE SCR., - SCREEN S.C.R. - SHOWER CURTAIN ROD S.D. - SOAP DISPENSER

SECT. - SECTION SEP. - SEPARATE SH. - SHEET SHOWER SHV. - SHELF. SHELVES SIM - SIMILAR SL - SLOPE S.M. - SHEET METAL S.N.D. - SANITARY NAPKIN DISPENSER

S.N.T.D. - SANITARY NAPKIN & TAMPON DISPOSER SP. - SPACES SPEC. (S) - SPECIFICATIONS SQ. - SQUARE S.S. - STAINLESS STEEL, SERVICE SINK STL. - STEEL

ST. - STORAGE STD. - STANDARD STRUCT. - STRUCTURAL SUP. - SUPPORT SUSP. - SUSPENDED SYS - SYSTEM

T & G - TONGUE AND GROOVE T.B. - TOWEL BAR T.C. - TOP OF CURB T.D. - TILE DRAIN TEMP. - TEMPERATURE THK. - THICK T.O.B. - TOP OF BEAM T.O.S. - TOP OF STEEL T.T.D. - TOILET TISSUE DISPENSER T.W. - TOP OF WALL TYP. - TYPICAL

U.H. - UNIT HEATER U.N.O. - UNLESS NOTED OTHERWISE V. - VENT V.C.T. - VINYL COMPOSITION TILE VERT, - VERTICAL (LY)

## SYMBOLS LEGEND

Room name ROOM DESIGNATION

DOOR NUMBER

WALL TAG

WINDOW TYPE

DETAIL

SHOWN

INTERIOR ELEVATION

PLAN NUMBER SHEET ON WHICH PLAN IS

INTERIOR ELEVATION NUMBER (A101) SHEET ON WHICH ELEV IS SHOWN


(101)

-


(11)

**BUILDING SECTION** 

ENLARGED PLAN



WALL SECTION



## GENERAL NOTES / SPECIAL REQUIREMENTS:

- 1. CONTRACTOR AND SUBCONTRACTORS SHALL REVIEW, CHECK, AND VERIFY ALL DRAWINGS, DIMENSIONS, DETAILS, AND EXISTING SITE CONDITIONS FOR ACCURACY AND CONFORMANCE WITH SPECIFICATIONS PRIOR TO PROCEEDING WITH THE WORK
- 2. ANY DISCREPANCY IN THE DRAWINGS AND DIMENSIONS OR VARIATIONS BETWEEN EXISTING CONDITIONS AND THAT SHOWN ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER FOR INSTRUCTION PRIOR TO START OF PROJECT.
- 3. ANY NECESSARY WORK ACTIVITIES NOT SHOWN OR DETAILED ON THE DRAWINGS BUT IS WITHIN THE WORK LIMITS AS INDICATED ON THE DRAWINGS SHALL BE CONSIDERED TO BE PART OF THE CONTRACT WORK AND SHALL NOT BE ELIGIBLE FOR CHANGE ORDERS.
- 4. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK IN SUCH A FASHION AS NOT TO DISRUPT UTILITY SERVICES TO THE OWNER OR OWNER'S OCCUPANTS, ANY DAMAGE AND SUBSEQUENT REPAIRS TO EXISTING SYSTEMS SHALL BE THE SOLE RESPONSIBILITY OF THE
- 5. CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY CLEANING OF THE WORK SITE AND ALL CLEANING OF FLOORS OUTSIDE THE WORKING LIMITS AS DIRECTED AND TO THE SATISFACTION OF THE ENGINEER.  $\ \ \bigtriangleup$
- 6. THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS REPRESENTED HEREIN DO NOT INDICATE THE METHOD OR MEANS OF CONSTRUCTION ACTIVITIES.
- 7. THE CONTRACT SPECIFICATIONS AND DRAWINGS REPRESENT AND SHALL BE CONSIDERED ONE COMPLETE SET OF CONSTRUCTION DOCUMENTS.

ITEMS	UNIT	TOTAL
ROOF DRAIN COLLECTION NETWORK	ĻF	88
MASONRY CLEANING AND TUCKPOINTING	\$F	4,265
ROOF REPLACEMENT, LOCATION 1	LS	1
ROOF DECK CONCRETE CORNER REPAIR	LŞ	1
MASONRY FACE BRICK REPAIR	ŞF	60
MASONRY SEALER	SF	4,265
MODIFICATION AND PAINTING OF FIRE ESCAPE	LS	1
ROOFING SAMPLING AND ACM IDENTIFICATION	LS	1
HANDLING OF ASBESTOS CONTAINING MATERIALS (ACM)	LS	1
MOBILIZTION	~\\$~	h1-
MECHANICAL WORK, COMPLETE	LS	1 }

<b>CP</b> HANSON
Hanson Prefessional Services Inc.

JSER NAME =	DESIGNED - LOF	REVISED /1\09/04/12 ADDENDUM 1	ĺ
	DRAWN - BRK	REVISED	ĺ
LOT SCALE =	CHECKED - GLC	REVISED	
PLOT DATE =	APPROVED - GLC	REVISED	ĺ
			4

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

ABBREVIATIONS, SYMBOLS LEGEND AND TOTAL BILL OF MATERIALS			F.A.P. RTE.	SECTION	*******	
				2012-0451	I	
				I		1
Scale	SHEET NO 3 OF 11 SHEETS	Station From	Station To	1	HILIMONE FEE .	<u>.</u>

COUNTY TOTAL SHEE

WALL 11 003 CONTRACT NO. 60V37