


SUMMARY OF QUANTITIES

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0003	BRIDGE 80% FEDERAL 20% LOCAL 0008	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021	LOCAL 0% FEDERAL 100% LOCAL 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,708	1,708					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,342	1,342					
20100500	TREE REMOVAL, ACRES	ACRE	1.50	1.50					
20101000	TEMPORARY FENCE	FOOT	363	363					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	72,291	72,081		210			
20400800	FURNISHED EXCAVATION	CU YD	23,213	23,213					
20800150	TRENCH BACKFILL	CU YD	465	465					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	37,701	37,701					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	53,940	53,940					
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	2,961	2,961					
25000210	SEEDING, CLASS 2A	ACRE	7.50	7.50					
25000312	SEEDING, CLASS 4A	ACRE	1.75	1.75					
25000314	SEEDING, CLASS 4B	ACRE	2.00	2.00					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,020	1,020					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,020	1,020					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,020	1,020					
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	51,582	51,582					
25100900	TURF REINFORCEMENT MAT	SQ YD	292	292					
25200110	SODDING, SALT TOLERANT	SQ YD	840	840					
25200200	SUPPLEMENTAL WATERING	UNIT	42	42					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,070	1,070					
28000305	TEMPORARY DITCH CHECKS	FOOT	150	150					
28000400	PERIMETER EROSION BARRIER	FOOT	12,560	12,560					
28000500	INLET AND PIPE PROTECTION	EACH	16	16					
28000510	INLET FILTERS	EACH	92	92					
28100105	STONE RIPRAP, CLASS A3	SQ YD	289	289					
28100107	STONE RIPRAP, CLASS A4	SQ YD	127	127					
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	82		82				
28100709	STONE DUMPED RIPRAP, CLASS A5	SQ YD	12			12			
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	3	3					
28200200	FILTER FABRIC	SQ YD	573	400	173				
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	2,380	2,380					
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	34,962	34,962					
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3,203	3,203					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1,728	1,728					
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SQ YD	820	820					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3,943	3,943					
40600300	AGGREGATE (PRIME COAT)	TON	79	79					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	79	79					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	439	439					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	715	715					

- SPECIALTY ITEM
- X CONSTRUCTION TYPE CODE 0042

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 7/23/2012 10:10:07 AM
 FILE NAME: 090071-sum.dgn
 PLOT DRIVER: acadprt
 PEN TABLE: standard.ctb


HRGreen.com
 Illinois Professional Design Firm
 # 194-001322

USER NAME = jsteno	DESIGNED - JPA	REVISED -
FILE NAME = 090071-sum.dgn	DRAWN - SVJ	REVISED -
PLOT SCALE = N.T.S.	CHECKED - JLP	REVISED -
PLOT DATE = 7/23/2012	DATE - 7/23/12	REVISED -

MCHENRY COUNTY
DIVISION OF TRANSPORTATION

SUMMARY OF QUANTITIES
CHARLES J. MILLER ROAD ROADWAY IMPROVEMENTS

F.A.U. RTE. 3860	SECTION 09-00372-00-PW	COUNTY MCHENRY	TOTAL SHEETS 252	SHEET NO. 4
CONTRACT NO. 63633			ILLINOIS FED. AID PROJECT	

SCALE: N.T.S. SHEET NO. 1 OF 7 SHEETS STA. _____ TO STA. _____