


**SUMMARY OF QUANTITIES (CONTINUED)**

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0003	BRIDGE 80% FEDERAL 20% LOCAL 0008	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021	LOCAL 0% FEDERAL 100% LOCAL 0021
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	17	17					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	3	3					
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	21	21					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	10	10					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	3	3					
60500050	REMOVING CATCH BASINS	EACH	3	3					
60500060	REMOVING INLETS	EACH	8	8					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1	1					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	8,616	8,616					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6,482	6,482					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	10,478	10,478					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	8,319	8,319					
60624600	CORRUGATED MEDIAN	SQ FT	815	815					
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	987.5	800.0					187.5
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1,187.5	1,187.5					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3					
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6					
63200310	GUARDRAIL REMOVAL	FOOT	415	415					
* 66400305	CHAIN LINK FENCE, 6'	FOOT	20						20
* 66401900	CHAIN LINK GATES, 5' X 6' SINGLE	EACH	2						2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18					
67100100	MOBILIZATION	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	403	403					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	39	39					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,662	4,662					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	370	370					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	56,120	56,120					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,065	1,065					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,970	1,970					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	445	445					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	125	125					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12,255	12,255					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,060	3,060					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	499	499					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	137	137					
72000100	SIGN PANEL - TYPE 1	SQ FT	551	545			6		
72000200	SIGN PANEL - TYPE 2	SQ FT	60	35			25		

- \* SPECIALTY ITEM
- X CONSTRUCTION TYPE CODE 0042

COMPANY NAME: HRGreen.com  
 PROJECT CONTACT: J. Jettano  
 CLIENT: MCHENRY COUNTY  
 DATE: 7/23/2012  
 FILE NAME: 090071-sum.dgn  
 PLOT SCALE: N.T.S.  
 PLOT DATE: 7/23/2012  
 PLOT DEVER: pdf, dxf  
 PEN TABLE: standard-trans.tbl



**HRGreen.com**  
 Illinois Professional Design Firm  
 # 184-001522

USER NAME = jettano	DESIGNED - JPA	REVISED -
FILE NAME = 090071-sum.dgn	DRAWN - SVJ	REVISED -
PLOT SCALE = N.T.S.	CHECKED - JLP	REVISED -
PLOT DATE = 7/23/2012	DATE - 7/23/12	REVISED -

**MCHENRY COUNTY  
DIVISION OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
CHARLES J. MILLER ROAD ROADWAY IMPROVEMENTS**

SCALE: N.T.S. SHEET NO. 4 OF 7 SHEETS STA. TO STA.

F.A.U. RTE. 3860	SECTION 09-00372-00-PW	COUNTY MCHENRY	TOTAL SHEETS 252	SHEET NO. 7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63633	