



**EROSION CONTROL LEGEND**

SEEDING CLASS 2A EXCELSIOR BLANKET (NAG 75)	
SEEDING CLASS 4 EXCELSIOR BLANKET (NAG 75)	
STORM SEWER INLET PROTECTION -- INLET FILTER BASKET	
STONE RIP RAP CLASS A	
PERIMETER EROSION BARRIER	
TEMPORARY CONSTRUCTION FENCE	
DITCH CHECK -- GEO-RIDGE	
SEDIMENT TRAP WITH CORR ROLL	

**NOTES:**  
 TEMPORARY SEEDING SHALL BE INITIATED AFTER 7 DAYS IF AN AREA IS TO SIT IDLE FOR MORE THEN 14 DAYS. COST OF TEMPORARY EROSION CONTROL SEEDING SHALL BE CONSIDERED INCLUDED IN THE COST OF SEEDING CLASS 2A.  
 DURING CONSTRUCTION CONTRACTOR SHALL CONSTRUCT AND MAINTAIN SEDIMENT TRAPS WITH CORR ROLLS AT EACH LOCATION SPECIFIED. UPON FINAL RESTORATION THE SEDIMENT TRAPS SHALL BE CLEANED OUT AND STONE RIP RAP AND FABRIC SHALL BE INSTALLED. COST OF SEDIMENT TRAPS SHALL BE INCLUDED IN THE COST OF STONE RIP RAP.

MATCH LINE STA. 199+00  
SEE ABOVE RIGHT

MATCH LINE STA. 203+50  
SEE SHEET 14

FILE NAME = 4459.000-PR3.dwg	USER NAME = GEORGE WHITTEN	DESIGNED - KLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SOIL EROSION AND SEDIMENT CONTROL PLANS BIG TIMBER ROAD STA. 195+00 TO STA. 203+50</b>			FAP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1" = .0833'	CHECKED - KLB	REVISED -					527	08-00369-00-SP	KANE	67	13
PLOT DATE = 3/21/2012	DATE - 3/21/2012	REVISED -	REVISED -	SCALE 1"=20'	SHEET NO.	OF	SHEETS	STA.	TO	STA.	CONTRACT # 83669	ILLINOIS FED. AID PROJECT