

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005	0042
	20101700	SUPPLEMENTAL WATERING	UNIT	3	3	
	20200100	EARTH EXCAVATION	CU YD	1562	1562	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	729	729	
	30300112	AGGREGATE SUBGRADE IMPROVEMENT-12"	SQ YD	4537	4537	
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12722	12722	
	40600300	AGGREGATE (PRIME COAT)	TON	1273	1273	
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2840	2840	
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	849	849	
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7710	7710	
	42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	4683	4683	
	42001300	PROTECTIVE COAT	SQ YD	5708	5708	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1019	1019	
	42400800	DETECTABLE WARNINGS	SQ FT	152	152	
	44000100	PAVEMENT REMOVAL	SQ YD	4683	4683	
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	63609	63609	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	11	11	
	44000600	SIDEWALK REMOVAL	SQ FT	1002	1002	
	44003100	MEDIAN REMOVAL	SQ FT	20	20	
	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	6	6	
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	18	18	
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	55	55	
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1387	1387	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	91	91	

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005	0042
	60255500	MANHOLES TO BE ADJUSTED	EACH	3	3	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	20	20	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
	67100100	MOBILIZATION	L SUM	1	1	
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	12000	12000	
	* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	879	879	
	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34924	34924	
	* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1451	1451	
	* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1854	1854	
	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	194	194	
	* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	356	356	
	* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1156	1156	
	* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1559	1559	
	* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	47	47	
	* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	109	109	
	* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100	
	* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2158	2158	
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10	

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 11617-QUAN-01 - IDOT.P01

USER NAME =

DESIGNED - JH

CHECKED - HLG

PLOT SCALE =

PLOT DATE = 05-02-12

REVISED -

REVISED -

DRAWN - MED

REVISED -

CHECKED - AG

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

TAYLOR ROAD  
ROADWAY RESURFACING  
SUMMARY OF QUANTITIES & GENERAL NOTES

SCALE: SHEET NO. 2 OF 26 SHEETS STA. TO STA.

F.A.U.  
RTE.

0286

SECTION

12-00099-00-RS

COUNTY

WILL

TOTAL  
SHEETS

26

SHEET  
NO.

2

CONTRACT NO. 63727

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-0003(021)