


NOTES:
1. APPROXIMATELY 100 RAISED REFLECTIVE PAVEMENT MARKERS ARE TO BE REMOVED EAST OF WEBER ROAD. THESE MARKERS WILL NOT BE REPLACED.

LEGEND

- BUTT JOINT
- EXISTING MANHOLE
- EXISTING CATCH BASIN
- COMBINATION B-6.24 CURB AND GUTTER REMOVAL AND REPLACEMENT
- HMA SIDEWALK REMOVAL & P.C. CONCRETE SIDEWALK REPLACEMENT
- P.C. CONCRETE SIDEWALK REMOVAL AND REPLACEMENT (5")
- PAVEMENT REMOVAL WITH CLASS D PATCH, 10"
- STRUCTURE TO BE ADJUSTED
- PAVEMENT REMOVAL WITH PCC PAVEMENT, 10" (JOINTED) REPLACEMENT
- DETECTOR LOOP TO BE REPLACED



FILE NAME = 11617-PLAN-01 - IDOT P02

USER NAME =	DESIGNED -- JH	REVISED --
	CHECKED -- HLG	REVISED --
PLOT SCALE =	DRAWN -- ACAD	REVISED --
PLOT DATE = 05-02-12	CHECKED -- ACAD	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TAYLOR ROAD ROADWAY RESURFACING PAVEMENT PLAN	
SCALE:	SHEET NO. 8 OF 26 SHEETS STA. TO STA.

F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0206	12-00059-00-RS	WILL	26	8
CONTRACT NO. 63727				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-4003(021)				