


SUMMARY OF QUANTITIES				URBAN	L1CE					L01E					10% STATE			L01E		100% VILLAGE OF MORTON
					ROADWAY FAI 74 / FAI 155	I-155 OVER I-74 (RAMPS G & H)	I-74 OVER ABANDONED RAILROAD DEMOLITION	I-74 OVER JEFFERSON ST	I-74 OVER US 150 (JACKSON ST)	I-74 / I-155	MORTON AVE. OVER I-74	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSCAPING	INTELLIGENT TRANSPORTATION SYSTEM	PINECREST DR PLANS	EMERGENCY VEHICLE PRE-EMPTION		
CODE	ITEM	UNIT	TOTAL QUANTITY	0003	0008	0044	0010	0010	0040	0014	0021	0021	0021	0031	0021	0014	0021			
78300100	PAVEMENT MARKING REMOVAL	SO FT	38,525	38,525																
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	4									3					1			
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	2														2			
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	45,711														45,711			
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	22,358								3,129	2,141					17,088			
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	430								200						230			
81028380	UNDERGROUND CONDUIT, PVC, 3 1/2" DIA.	FOOT	433								433									
81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	290									290								
81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/4" DIA.	FOOT	250	250																
81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	300	300																
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	15,989									14,869					1,120			
81300555	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 8"	EACH	24									24								
81304035	JUNCTION BOX EMBEDDED IN STRUCTURE 8" X 24" X 10"	EACH	6									6								
81400200	HEAVY-DUTY HANDHOLE	EACH	24	4													20			

* SPECIALTY ITEM

FILE NAME : ...General\0468620-sht-500_21.dgn	DESIGNED - EJA	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME : jreabillio	DRAWN - TMB	REVISED -						90-(14R)(14HB-4,14,14HB)BR	TAZEWELL	2433	28	
PLT DATE : 7/30/2012	CHECKED - JNR	REVISED -			SCALE: NTS	SHEET NO. 21 OF 34 SHEETS	STA.	TO STA.	CONTRACT NO. 68620		ILLINOIS FED. AID PROJECT	
DATE - JULY 20, 2012	REVISOR -	REVISED -										