

SIGN INDEX #	SIGN CODE	STA	OFFSET	DTL SHT #	ALIGNMENT	DIRECTION	EX OVRHD STR	EX STANDARD	EX SPECIAL	TEMP STD	TEMP SPCL	PROPOSED	DESCRIPTION	NEW STA.	NEW OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATIONS MOUNT	TEMPORARY SIGN PANEL ASSEMBLY	TEMPORARY SIGN PANEL OVERLAY
																EACH	EACH	EACH	EACH	SQ FT	SQ FT
21.03	W4-1L	13+16.00	65.88	-	I-155	SB		X					MERGE								16
21.12	W13-3	13+19.00	-82.04	-	I-155	NB		X					40 MPH RAMP								20
21.05-1	R2-1	19+16.00	100.77	-	I-155	SB		X					65 MPH			0.50					
21.05-2	R2-I102	19+16.00	100.77	-	I-155	SB		X					45 MPH MIN			0.50					
23.02	W4-1L	48+79.82	-72.76	-	I-155	NB		X					MERGE								16
2.01-1	R2-1	453+60.00	87.35	-	I-74	EB		X					SPEED LIMIT - 65								20
2.01-2	R2-I102	453+60.00	87.35	-	I-74	EB		X					SPEED LIMIT - MIN 45								12
6.06-1	R2-1	510+00.00	-68.50	-	I-74	WB		X					SPEED LIMIT - 65			0.50					
6.06-2	R2-I102	510+00.00	-68.50	-	I-74	WB		X					SPEED LIMIT - MIN 45			0.50					
7.01	D9-I105	525+04.00	12.33	-	I-74	EB			X				EXIT 101 W/ ARROW	502+45.00	44.00		2	2	RELOCATE		
12.01	W13-3	584+39.00	97.25	-	I-74	EB		X					RAMP SPEED 50 MPH				1.00				
12.03	E5-1A	585+61.65	62.84	-	I-74	EB		X					EXIT 102 A	580+45.00	48.00			2	2	RELOCATE	
12.05	D10-6	586+30.08	62.41	-	I-74	EB		X					MILE MARKER 102	587+89.97	62.66	1.00					RELOCATE
12.04	W4-1R	588+57.00	-65.87	-	I-74	WB		X					MERGE	588+64.32	-69.80		1.00				RELOCATE
4T.01				266	I-74	EB				X			I-74 USE LEFT LANE	480+00.00	6.43						10
4T.02				266	I-74	EB				X			I-155 USE RIGHT LANE	480+00.00	77.82						11
17.03	R3-I031	28+00.00	-0.26	-	MORTON	NB			X				2 ARROWS AHEAD, 1 ARROW TURN								6
18.03	R3-I033	31+01.00	43.54	-	MORTON	NB			X				2 ARROWS AHEAD, 1 ARROW TURN ONLY	29+00.00	55.27	1.00				RELOCATE	
17T.03				272	MORTON	NB				X			LEFT LANE ARROW UP, RIGHT LANE UP/RIG	28+01.70	-0.26						6
18T.03				272	MORTON	NB				X			LEFT LANE ARROW UP, RT LANE UP/RT ON	29+30.00	39.50						6
14.06	W13-3	204+52.40	21.50	-	MORTON RAMP B	-		X					RAMP SPEED 40 MPH								20
TOTALS															2	4	4	4	34	110	

TEMPORARY SIGN SCHEDULE