LOCATION ROAD	STATION FROM	STATION TO	AGGREGATE SUBGRADE IMPROVEMENT 8" SQ YD	AGGREGATE SUBGRADE IMPROVEMENT 12" SQ YD	STABILIZED SUBBASE HOT-MIX ASPHALT, 4" SQ YD	AGGREGATE SHOULDERS, TYPE B 6" SQ YD	PORTLAND CEMENT CONCRETE SHOULDERS 11" SQ YD	PIPE UNDERDRAINS 4" FOOT	TEMPORARY PAVEMENT REMOVAL SQ YD	AGGREGATE SHOULDER REMOVAL CU YD	WHITEWASHING FOR CONCRETE PAVEMENT SQ YD	TEMPORARY PAVEMENT SQ YD
I-474	-	456+00.00										
I-74	456+00.00	471+00.00										
I-74	471+00.00	486+00.00										
I-74	486+00.00	501+00.00										
I-74	501+00.00	516+00.00										
I-74	516+00.00	531+00.00										
RAMP G/H	118+50.00	101+47.00										
I-74	531+00.00	546+00.00										
I-74	546+00.00	561+00.00										
I-74	561+00.00	576+00.00										
I-74	576+00.00	591+00.00										
I-74	591+00.00	606+00.00										
I-74	606+00.00	621+00.00										
I-74	621+00.00	636+00.00										
I-74	636+00.00	640+00.00										
I-155	00+00.00	09+00.00										
I-155	09+00.00	23+00.00										
I-155	23+00.00	37+50.00										
I-155	37+50.00	51+00.00										
I-155	51+00.00	66+00.00										
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	0
Morton Ave.	36+50.00	44+75.00	0	0	0	0	0	0	31	2	0	146
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0
		TOTALS	0	0	0	0	0	0	31	2	0	146

	GLARE SCREEN (NEW LOCATION) FOOT	GLARE SCREEN TO REMAIN FOOT	GLARE SCREEN ON-SITE (MORTON) FOOT	TEMPORARY CONCRETE BARRIER (NEW LOCATION) FOOT	TEMPORARY CONCRETE BARRIER TO REMAIN FOOT	TEMPORARY CONCRETE BARRIER ON-SITE (MORTON) FOOT
			0			1250.0
			GLARE SCREEN FROM PREVIOUS STAGE (MORTON) FOOT			TEMPORARY CONCRETE BARRIER FROM PREVIOUS STAGE (MORTON) FOOT
			0			1962.0
			RELOCATE MODULAR GLARE SCREEN SYSTEM FOOT			RELOCATE TEMPORARY CONCRETE BARRIER FOOT
			0			650.0
	0	0	MODULAR GLARE SCREEN SYSTEM FOOT	0.0	0.0	TEMPORARY CONCRETE BARRIER FOOT
	0	0		137.5	337.5	
	0	0		512.5	262.5	
	0	0		0.0	0.0	
TOTALS	0	0	0	650.0	600.0	0.0

LOCATION ROAD	STATION FROM	STATION TO	PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS SQ FT	PAVEMENT MARKING TAPE, TYPE III 4" FOOT	PAVEMENT MARKING TAPE, TYPE III 8" FOOT	PAVEMENT MARKING TAPE, TYPE III 12" FOOT	PAVEMENT MARKING TAPE, TYPE III 24" FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	POLYUREA PAVEMENT MARKING TYPE II LINE 4" FOOT	POLYUREA PAVEMENT MARKING TYPE II LINE 8" FOOT	POLYUREA PAVEMENT MARKING TYPE II LINE 12" FOOT
I-474	-	456+00.00									
I-74	456+00.00	471+00.00									
I-74	471+00.00	486+00.00									
I-74	486+00.00	501+00.00									
I-74	501+00.00	516+00.00									
I-74	516+00.00	531+00.00									
RAMP G/H	118+50.00	101+47.00									
I-74	531+00.00	546+00.00									
I-74	546+00.00	561+00.00									
I-74	561+00.00	576+00.00									
I-74	576+00.00	591+00.00									
I-74	591+00.00	606+00.00									
I-74	606+00.00	621+00.00									
I-74	621+00.00	636+00.00									
I-74	636+00.00	640+00.00									
I-155	00+00.00	09+00.00									
I-155	09+00.00	23+00.00									
I-155	23+00.00	37+50.00									
I-155	37+50.00	51+00.00									
I-155	51+00.00	66+00.00									
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0
Morton Ave.	36+50.00	44+75.00	18	2208	78	34	40	635	0	0	0
Morton Ave.	44+75.00	58+00.00	62	4058	0	613	15	1819	0	0	0
		TOTALS	79	6266	78	647	55	2454	0	0	0

	SHORT TERM PAVEMENT MARKING FOOT	CHANGEABLE MESSAGE SIGN CAL MO
TOTAL STAGE 4B	352	3.25

ATTENUATOR LOCATION SCHEDULE ROAD	STATION	OFFSET	TYPE	IMPACT ATTENUATORS WIDE NEW OR RELOCATED EACH	IMPACT ATTENUATORS WIDE TO REMAIN EACH	IMPACT ATTENUATORS NARROW NEW OR RELOCATED EACH	IMPACT ATTENUATORS NARROW TO REMAIN EACH
MORTON	31+64.18	10.16	NARROW		0	1	0
MORTON	41+23.76	14.94	WIDE	1	0	0	0

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDRCTVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDRCTVE, NARROW TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDRCTVE, TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (NON-REDRCTVE), TEST LVL 2
WIDE	1	0	2	0	-	-	1
NARROW	1	0	2	-	0	1	-

NOTE

MORTON STAGE 4 SUB STAGE B INDEPENDENT FROM I-74/I-155 STAGE 4

FILE NAME =	DESIGNED - HTL	REVISED -
D468620-sht-schedule-B-04.dgn	DRAWN - KV	REVISED -
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -
PLOT DATE = 7/29/2012	DATE - 7/20/2012	REVISED -

TERRA ENGINEERING LTD.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
STAGE 4 – SUB STAGE B – SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. 33 OF 85 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	90-[14R;(14HB-4,14,14HVB)BR]	TAZEWELL	2433	109

CONTRACT NO. 68620

ILLINOIS FED. AID PROJECT

• 74 & 155