

SIGN INDEX #	SIGN CODE	STA	OFFSET	DTL SHT #	ALIGNMENT	DIRECTION	EX OVRHD STR	EX STANDARD	EX SPECIAL	TEMP STD	TEMP SPCL	PROPOSED	DESCRIPTION	NEW STA.	NEW OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATIONS - GROUND MOUNT	TEMPORARY SIGN PANEL ASSEMBLY	TEMPORARY SIGN PANEL OVERLAY	CONSTRUCT PROPOSED SIGN (SEE SIGN PLAN)
																EACH	EACH	EACH	SQ FT	SQ FT	
4.07-2.3		482+48.00		264	I-74	EB					X		OVERLAY - "LEFT 2 LANES"						RELOCATE		
4.07-2.4		482+48.00		264	I-74	EB					X		OVERLAY - "RIGHT LANE ONLY"						RELOCATE		
3.01-2.3		460+42.00		264	I-74	EB					X		OVERLAY - "LEFT 2 LANES"						RELOCATE		
3.01-2.4		460+42.00		264	I-74	EB					X		OVERLAY - "RIGHT LANE ONLY"						RELOCATE		
3DG.02		462+25.00	-77	265	I-74	WB					X		DETOUR SIGN, I-155 SOUTH KEEP RIGHT						REMOVE		
3DG.01		455+25.00		265	I-74	EB					X		DETOUR SIGN, I-155 SOUTH KEEP RIGHT						REMOVE		
2T.03-0.3		-	-	264	I-74	EB					X		OVERLAY - "KEEP RIGHT"	442+31.05	-5.63					10	
2T.04-0.3		-	-	264	I-74	EB					X		OVERLAY - "KEEP RIGHT"	442+31.19	102.02					10	
9.03-0.1		500+00.00	81.5	268	I-74	EB					X		"1-1/2" OVERLAY						REMOVE		
PR9.03		535+00.00	11	-	I-74	EB					X		PROPOSED MORTON EXIT 1 MILE	PR	PR				RELOCATE	X	
5DG.02		495+00.00	-77	265	I-74	WB					X		DETOUR SIGN, I-155 SOUTH KEEP RIGHT						REMOVE		
7.01	D9-1105	514+60.00	7.18	-	I-74	EB					X		EXIT 101 W/ ARROW								
7DG.02		525+00.00	-74.5	265	I-74	WB					X		DETOUR SIGN, I-155 SOUTH KEEP RIGHT						REMOVE		
PR7.01		-	-	-	I-74	EB					X		EXIT 101 W/ ARROW	PR	PR					X	
PR7.02	W4-3R	-	-	-	I-74	WB					X		TWO WAY TRAFFIC	PR	PR					X	
PR9.01		-	-	-	I-74	EB					X		MILE MARKER	PR	PR					X	
PR9.02		-	-	-	I-74	WB					X		EXIT 101 W/ ARROW	PR	PR					X	
PR9.08		-	-	-	I-74	WB					X		EXIT 101 I-155 LINCOLN W/ ARROW	PR	PR					X	
10.02-0.1		556+77.00		268	I-74	WB					X		EXIT CLOSED						REMOVE		
11DH.01		572+09.00	66.89	270	I-74	EB					X		DETOUR SIGN I-74 WEST, PEORIA 1/4 MILE					REMOVE			
13.02	W4-1	599+76.00	-66.17	-	I-74	WB					X		MERGE						REMOVE		
13.11	W13-3	597+99.00	106.31	-	I-74	EB					X		RAMP SPEED 25 MPH			1.00					
15T.02		628+98.52	-85.92	271	I-74	WB					X		RIGHT LANE EXIT ONLY						REMOVE		
21.14-0.1		17+68.00		272	I-155	NB					X		OVERLAY "EXIT CLOSED"						REMOVE		
22DH.02		31+00.00	-80.74	273	I-155	NB					X		DETOUR SIGN I-74 WEST, PEORIA W/ ARROW					REMOVE			
22.02-0.1		35+30.00		272	I-155	NB					X		EXIT CLOSED						REMOVE		
PR21.03	W4-1L	-	-	-	I-155	SB					X		MERGE	PR	PR					X	
PR21.05-1	R2-1	-	-	-	I-155	SB					X		65 MPH	PR	PR					X	
PR21.05-2	R2-1102	-	-	-	I-155	SB					X		45 MPH MIN	PR	PR					X	
22.01	D2-2	23+05.00	11.03	-	I-155	SB					X		MORTON EXITS				3	3			
PR22.01		-	-	-	I-155	SB					X		MORTON EXITS IL 98, BIRCH., QUEENWOOD	PR	PR					X	
22.09	D2-2	29+28.00	96.89	-	I-155	SB					X		LINCOLN DECATUR DISTANCE				2	2			
PR22.09	D2-2	-	-	-	I-155	SB					X		LINCOLN DECATUR DISTANCE	PR	PR					X	
22.05-1	M3-3	27+10.56	90.56	-	I-155	SB					X		SOUTH			0.50					
22.05-2	M1-1	27+10.56	90.56	-	I-155	SB					X		I-155 ROUTE SHIELD			0.50					
PR22.05-1	M3-3	-	-	-	I-155	SB					X		SOUTH	PR	PR					X	
PR22.05-2	M1-1	-	-	-	I-155	SB					X		I-155 ROUTE SHIELD	PR	PR					X	
22.07	M1-10	27+14.00	95.06	-	I-155	SB					X		EISENHOWER SYSTEM SIGN			1.00					
PR22.07		-	-	-	I-155	SB					X		EISENHOWER SYSTEM SIGN	PR	PR					X	
PR21.08	D10-5	-	-	-	I-155	NB					X		MILE MARKER 32	PR	PR					X	
18T.05		32+60.00	45.08	272	MORTON	NB					X		DUAL LEFT ARROWS Y, DUAL STRAIGHT ARROWS						REMOVE		
19T.01		40+00.00	44.3	272	MORTON	NB					X		I-74 WEST PEORIA LEFT ARROW						REMOVE		
19.01	D1-1038	38+31.00	72.22	-	MORTON	NB					X		I-74 W PEORIA ARROW						REMOVE		
PR9.17	W13-3	-	-	-	I-155	NB					X		50 MPH RAMP	PR	PR					X	
PR21.18		-	-	-	I-155	NB					X		LANE ENDS MERGE RIGHT	PR	PR					X	
PR22.04		-	-	-	I-155	NB					X		MERGE RIGHT	PR	PR					X	
22.02	D1-1002	35+30.00	-120.8	-	I-155	NB					X		I-74 W PEORIA KEEP LT/ I-74 E BLOOM KEEP RT				2	2			
PR22.06	W9-1	-	-	-	I-155	NB					X		LEFT LANE ENDS	PR	PR					X	
PR22.02		-	-	-	I-155	NB					X		I-74 W PEORIA KEEP LT/ I-74 E BLOOM KEEP RT	PR	PR					X	
TOTALS																3	7	7	0	20	0

**TEMPORARY SIGN SCHEDULE**

FILE NAME = D468620-shr-sign02-12WS2.dgn	DESIGNED - HTL	REVISED -		<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>MAINTENANCE OF TRAFFIC</b> <b>2014 WINTER SHUTDOWN SIGN SCHEDULE</b>	F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = TERRA	DRAWN - KV	REVISED -				* 90-[14R(14HB-4,14,14HVB)BR]	TAZEWELL	2433	146	
PLOT DATE = 7/18/2012	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
	DATE - 7/20/2012	REVISED -				SCALE:	SHEET NO. 70 OF 85 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	