

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	L20E STP(F) LS3E HSIP		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	L20E STP(F) LS3E HSIP	
				0005 80% FED 20% STATE	0021 90% FED 10% STATE					0005 80% FED 20% STATE	0021 90% FED 10% STATE
20200100	EARTH EXCAVATION	CU YD	483	483		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1	
25200100	SODDING	SO YD	315	315		60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	435	435	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	870	870		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	297	297	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1214	1214		67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	2	1
40600990	TEMPORARY RAMP	SO YD	670	670		67100100	MOBILIZATION	L SUM	1	1	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2428	2428		70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SO YD	717	717		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
42001200	PAVEMENT FABRIC	SO YD	717	717		70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
44000100	PAVEMENT REMOVAL	SO YD	19	19		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	25865	25865		70300100	SHORT TERM PAVEMENT MARKING	FOOT	10265	10265	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1106	1106		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1140	1140	
44022033	PARTIAL DEPTH REMOVAL 4"	SO YD	44	44		* 72000200	SIGN PANEL - TYPE 2	SO FT	72		72
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	9.8	9.8							
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	257	257							

\*SPECIALTY ITEM