

L2OE LS3E
STP(F) HSIP

L2OE LS3E
STP(F) HSIP

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	0021 90% FED 10% STATE
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	1047	1047	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10100	10100	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4770	4770	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	270	270	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	890	890	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	636	636	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	225	225	
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	15		15
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	71		71
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	358		358
81400100	HANDHOLE	EACH	2		2
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1591		1591
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1767		1767

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	0021 90% FED 10% STATE
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	326		326
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	688		688
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2		2
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1		1
87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	1		1
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21		21
87900200	DRILL EXISTING HANDHOLE	EACH	5		5
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8		8
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4

*SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
g:\pwwork\pwwork\staffennk\08247536\074510-eh1-eoq.dgn	74510-eh1-eoq.dgn	DRAWN -	REVISED -			320	126N	MACON	39	4	
	PLOT SCALE = 100.0000 1/2 in.	CHECKED -	REVISED -			CONTRACT NO. 74510					
	PLOT DATE = 6/29/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					