SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-0004 FUNDING 100% STATE UNIT	QUANTITY
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	13
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	1136
35501325	HOT-MIX ASPHALT BASE COURSE, 10 1/4"	SQ YD	346
40300100	BITUMINOUS MATERIAL (PRIME COAT)	GALLON	855
40600300	AGGREGATE (PRIME COAT)	TON	24
40600990	TEMPORARY RAMP	SQ YD	173
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1187
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	534
44000100	PAVEMENT REMOVAL	SQ YD	893
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	5428
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4610
48101200	AGGREGATE SHOULDERS, TYPE B	TON	87
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-0004 FUNDING 100% STATE UNIT	QUANTITY
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2230
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7661
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	12
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3309
* 78000650	THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	FOOT	12
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7661
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	31

*SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\greenleesm\d0312786\sjl to-ovr_soq_index.dgn	USER NAME = greenleesm	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
	PLOT DATE = 7/17/2012	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	09 CH BIT RES PATCH 2013-3	PULASKI	10	3

CONTRACT NO. 78329

ILLINOIS FED. AID PROJECT