F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT1 & PT2) R-1

SUMMARY OF QUANTITIES

				90% FEDERAL / 10% STATE									
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
					O16-W923	O16-W931	STR NO 016-0142	STR NO 016-1148					
CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	42,408	42,408									
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	7,213	7,213									
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	11,653	11,653									
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	1,563	1,563									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	30,530	30,530									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5,580	5,580									
• 72000100	SIGN PANEL-TYPE 1	SQ FT	102.5						102.5				
• 72000200	SIGN PANEL-TYPE 2	SQ FT	112.6						112.6				
• 72000300	SIGN PANEL - TYPE 3	SQ FT	871						871				
• 72400200	REMOVE SIGN PANEL ASSEMBLY-TYPE B	EACH	4						4				
• 72400330	REMOVE SIGN PANEL-TYPE 3	SQ FT	226						226				
• 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	652						652				
• 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	90.5						90.5				
• 73000100	WOOD SIGN SUPPORT	FOOT	98						98				
• 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	9						9				
• 73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	64						64				
• 73300300	OVERHEAD SIGN STRUCTURE - SPAN,TYPE III-A (5'-0" X 7'-0")	FOOT	66						66				
• 73302210	OVERHEAD SIGN STRUCTURE -CANTILEVER, TYPE III-C-A(36" X 7'-0")	FOOT	32.25						32.25				
• 73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	16						16				
• 73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	107						107				
• 73400100	CONCRETE FOUNDATIONS	CU YD	1.4						1.4				
• 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	48.9						48.9				
• 73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3						3				
• 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2						2				
• 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2						2				
• 73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	3						3				
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	199.7	199.7									
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	39,645	39,645									
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	11,612	11,612									
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	475	475									

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

SOQ-4

CTE | AECOM

6/6/2006 9:38:41 AM