F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	11
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT1 & PT2) R-1

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE									
					URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
						016-W923	016-W931	STR NO 016-0142	STR NO 016-1148					
					J000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	15,827	15,827									
*	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	2,660	2,660									
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	45	45									
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,351	1,351									
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6									
*	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	225	225									
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	17	17									
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	144	144									
*	78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	2	2									
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	15,434	15,434									
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	145									145	
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	190									190	
*	81016600	CONDUIT IN TRENCH, 2" DIA., HIGH DENSITY POLYETHYLENE COILABLE	FOOT	95									95	
*	81023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	180									180	
*	81200150	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	1,400									1,400	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4									4	
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	966								73	893	
*	C2011136	SHRUB, SYRINGA X PERSICA (PERSIAN LILAC) 3' HEIGHT, BALLED AND BURLAPPED	EACH	153	153									
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	379	379									
*	E20220G1	VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON IVY), 1-GALLON POT	EACH	273	273									
*	K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	2.33	2.33									
	X0320333	ROADWAY CLEANING (SPECIAL)	EACH	19	19									
	X0321720	WATER MAIN REMOVAL	FOOT	244	244									
*	X0321905	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, 12"	FOOT	143	143									
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1,788	1,788									
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	17	17									
	X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	7.8	7.8									
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	338	338									
*	X0323907	COMMUNICATIONS VAULT	EACH	2									2	
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	3,883	3,883									

* DENOTES SPECIALTY ITEMS

CTE | AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

S00-5

6/6/2006 9:36:41 AM