F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT) & PT2) R-1

SUMMARY OF QUANTITIES

				90% FEDERAL / 10% STATE									
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
					016-W923	016-W931	STR NO 016-0142	STR NO 016-1148					
CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	975	975									
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	21,595	20,946		649							
X0324112	BARRIER BASE	FOOT	6,933	6,933									
* X0324415	CONDUIT ENCASED, REINFORCED CONCRETE, 1-4" DIA., CNC	FOOT	53									53	
* X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	230									230	
X0324697	SOIL STABILIZERS	POUND	284,719	284,719									
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	460	460									
X0325085	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	205	205									
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	205	205									
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	1,660	1,660									
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	0.14	0.14									
X4210400	LUG SYSTEM REMOVAL	EACH	1	1									
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	10,493	10,493									
X6061003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48 (MODIFIED)	FOOT	396	396									
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	1,989	1,989									
X6065740	CONCRETE MEDIAN SURFACE, 5 INCH (MODIFIED)	SQ FT	2,070	2,070									
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	2,566	2,566									
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32" HEIGHT	FOOT	3,569	3,569									
X6640050	CHAIN LINK FENCE 42", ATTACHED TO STRUCTURE (SPECIAL)	FOOT	718		718								
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	8	8									
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1									
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	270	270									
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	70	70									
* X8100045	CONDUIT ENCASED, REINFORCED CONCRETE, 1-3" DIA., CNC	FOOT	73								73		
XX001854	STABILIZED SUB-BASE 6"	SQ YD	42,709	42,709									
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	8,189	8,189									
XX004201	PAVEMENT REINFORCEMENT 14"	SQ YD	29,253	29,253									
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4							4			
Z0030070	IMPACT ATTENUATOR (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2							2			

* DENOTES SPECIALTY ITEMS

CTE | AECOM

SOQ-6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

6/15/2006 9:38:42 AM

P:\04468\dlnls dfts 18 & 19\sfmatr 18ongerdfsq18000002a.sht