

F.A.I. RT.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	21
STA.	TO STA.			
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
60A62	* (1919.15, 2021-922 PT1 & PT2) R-1			

**ROADWAY ITEMS SCHEDULE**

STATION TO STATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRANULAR MATERIAL, TYPE B, 12"	SUB-BASE GRANULAR MATERIAL, TYPE B, 24"	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONC. PAVEMENT, 14"	SHOULDER RUMBLE STRIP	PCC SHOULDERS 14"	STABILIZED SUB-BASE, 6"	PAVEMENT REINFORCEMENT, 14"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)
	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ YD	TON	TON
6055+93.22 TO 4410+00.00	3,638	-	3,638	1,951	9,632	1,426	3,638	1,951	1.5	7.3
4410+00.00 TO 4420+00.00	4,115	-	4,115	2,621	3,337	1,248	4,115	2,621	1.7	8.3
4420+00.00 TO 4432+00.00	8,054	-	8,054	5,056	4,806	2,418	8,054	5,056	3.3	16.2
4432+00.00 TO 4444+00.00	7,591	-	7,591	5,574	4,025	1,577	7,591	5,574	3.1	15.2
4444+00.00 TO 4456+00.00	7,419	-	7,419	5,075	4,758	1,763	7,419	5,075	3.0	14.9
4456+00.00 TO 4468+00.00	8,041	2,238	5,804	6,231	4,201	1,289	8,041	6,231	3.3	16.1
4468+00.00 TO 4474+50.00	3,851	2,745	1,106	2,745	2,600	772	3,851	2,745	1.6	7.8
<b>TOTALS</b>	<b>42,709</b>	<b>4,983</b>	<b>37,727</b>	<b>29,253</b>	<b>33,399</b>	<b>10,493</b>	<b>42,709</b>	<b>29,253</b>	<b>17.5</b>	<b>85.8</b>

**CURB AND GUTTER SCHEDULE**

STATION TO STATION	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.24	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.48 (MODIFIED)	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24
	FOOT	FOOT	FOOT
6055+93.22 TO 4410+00.00	700	-	-
4410+00.00 TO 4420+00.00	136	-	113
4420+00.00 TO 4432+00.00	6	-	554
4432+00.00 TO 4444+00.00	-	-	382
4444+00.00 TO 4456+00.00	-	-	674
4456+00.00 TO 4468+00.00	-	396	60
4468+00.00 TO 4474+50.00	193	-	206
<b>TOTALS</b>	<b>1,035</b>	<b>396</b>	<b>1,989</b>

**MEDIAN SCHEDULE**

STATION TO STATION	SAND BACKFILL	CONCRETE MEDIAN SURFACE, 6" (SPECIAL)	CONCRETE MEDIAN SURFACE 5" (MODIFIED)
	CU YD	SQ FT	SQ FT
25+26.25 TO 27+92.28	-	-	728
27+92.28 TO 33+04.32	-	-	1,342
6055+93.22 TO 4410+00.00	-	2,464	-
4410+00.00 TO 4420+00.00	-	530	-
4420+00.00 TO 4432+00.00	-	307	-
4432+00.00 TO 4444+00.00	40	1,609	-
4444+00.00 TO 4456+00.00	132	2,232	-
4456+00.00 TO 4468+00.00	-	346	-
4468+00.00 TO 4474+50.00	-	807	-
<b>TOTALS</b>	<b>172</b>	<b>8,295</b>	<b>2,070</b>

REVISIONS	
NAME	DATE

SCH-2

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

**SCHEDULE OF QUANTITIES**

SCALE: NONE  
DATE: June 9, 2006

DRAWN BY: NJH  
CHECKED BY: RMG

6/5/2006 9:40:09 AM