F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	80
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT1 & PT2) R-1

SEWER REMOVAL ITEMS cont.

SHEET NUMBER	FROM		TO		STORM SEWER REMOVAL 10" (FT)	STORM SEWER REMOVAL 12" (FT)	STORM SEWER REMOVAL 15" (FT)	STORM SEWER REMOVAL 21" (FT)	STORM SEWER REMOVAL 36" (FT)	PIPE UNDERDRAIN REMOVAL (FT)	WATERMAIN REMOVAL (FT)	PLUG AND ABANDON EXISTING PIPE (CU YD)	TRENCH BACKFILL (CU YD)
	STATION	OFFSET	STATION	OFFSET									
DU-8	4433+24	9' LT	4433+31	11' LT	7								2.4
DU-8	4433+51	33' RT	4433+51	41' RT			8						3.2
DU-8	4435+05	10' LT	4435+07	29' RT	40								13.7
DU-8	4435+83	13' LT	4435+85	36' RT							49		0.0
DU-8	4436+02	60' RT	4436+09	58' RT			6						0.0
DU-8	4436+02	60' RT	4436+75	40' RT								3.1	0.0
DU-8	4436+70	8' LT	4436+71	14' LT	6								2.1
DU-8	4436+71	14' LT	4436+72	22' LT								0.2	0.0
DU-9	4436+75	40' RT	4436+86	37' RT								0.5	0.0
DU-9	4436+86	37' RT	4437+14	29' RT			30						12.2
DU-9	4437+16	35' RT	4437+15	30' RT			5						2.0
DU-9	4437+15	28' RT	4437+15	20' RT				8					0.0
DU-9	4437+16	29' RT	4437+63	27' RT			46						0.0
DU-9	4437+64	27' RT	4437+56	14' LT			42						17.0
DU-9	4437+56	14' LT	4437+54	26' LT								0.6	0.0
DU-9	4438+24	42' RT	4438+23	20' RT		22							0.0
DU-9	4438+23	19' RT	4438+22	15' LT	34								0.0
DU-9	4439+52	45' RT	4439+52	17' RT			28						0.0
DU-9	4439+53	15' RT	4439+63	18' LT			34						13.8
DU-9	4439+63	18' LT	4439+67	31' LT								0.6	0.0
DU-9	4440+72	45' RT	4440+86	19' RT		30							11.0
DU-9	4440+86	19' RT	4440+85	21' LT	39								0.0
DU-10	4442+05	45' RT	4442+05	42' RT						3			0.0
DU-10	4442+05	40' RT	4442+13	23' RT	19								4.4
DU-10	4442+13	22' RT	4442+02	23' LT		46							7.7
DU-10	4445+49	37' RT	4445+61	45' RT						15			0.0
DU-10	4445+48	36' RT	4445+48	28' RT	8								2.7
DU-10	4445+48	27' RT	4445+49	1' RT	26								8.9
DU-10	4445+50	0' RT	4445+58	1' LT	8								2.7
DU-10	4445+49	0' LT	4445+50	14' LT	14								4.8
DU-10	4445+50	14' LT	4445+50	26' LT								0.2	0.0
DU-11	4447+73	36' RT	4447+72	28' RT	9								3.1
DU-11	4447+72	27' RT	4447+69	1' RT	26								0.0
DU-11	4447+60	2' LT	4447+68	1' RT	8								2.7
DU-11	4447+69	1' RT	4447+69	9' LT	10								0.0
DU-11	4447+69	21' LT	4447+78	14' LT								0.3	0.0
DU-11	4449+73	46' RT	4449+72	12' LT							58		0.0
DU-11	4449+66	2' LT	4449+74	1' RT	8								2.7
DU-11	4449+75	1' RT	4449+82	3'LT	8								2.7
DU-11	4449+83	5' LT	4449+83	7' LT		2							0.0
DU-11	4449+77	39' RT	4449+77	27' RT	12								4.1
DU-11	4449+77	28' RT	4449+74	0' RT	27								9.2
DU-11	4450+37	28' RT	4450+47	37' RT	14								2.7
DU-11	4450+48	47' RT	4450+48	38' RT						9			0.0
DU-11	4450+48	38' RT	4450+47	1' RT			37						15.0
DU-11	4450+38	3' LT	4450+46	0' RT	8								1.7
DU-11	4450+47	0' RT	4450+50	6' LT		7							2.6
DU-11	4450+89	37' RT	4451+00	31' RT	12								4.1
DU-12	4451+00	31' RT	4451+06	28' RT	7								2.4
DU-12	4451+07	27' RT	4451+10	1' RT	27								9.2
DU-12	4451+01	3' LT	4451+09	0' LT	8								2.7
DU-12	4451+10	0' LT	4451+11	8' LT		8							2.9
DU-12	4451+11	8' LT	4451+11	12' LT								0.1	0.0
DU-12	4452+68	36' RT	4453+51	28' RT						83			0.0
DU-12	4453+51	36' RT	4453+51	28' RT	8								2.7
DU-12	4453+51	27' RT	4453+50	1' RT		26							0.0
DU-12	4453+51	0' RT	4453+59	1' LT		8							2.9
DU-12	4453+50	1' RT	4453+50	5' LT		6							0.0
DU-12	4454+78	47' RT	4454+78	38' RT						9			0.0
DU-12	4454+78	37' RT	4454+78	5' LT	42								0.0
DU-13	4456+77	36' RT	4457+61	27' RT						85			0.0
DU-13	4457+70	52' RT	4457+69	48' RT						4			0.0
DU-13	4457+68	46' RT	4457+61	28' RT	20								4.1
DU-13	4457+61	27' RT	4457+61	1' RT		26							4.0
DU-13	4457+52	1' LT	4457+60	0' RT	7								2.4
DU-13	4457+61	0' RT	4457+60	5' LT		5							0.0
DU-13	4459+60	62' RT	4459+60	58' RT						5			0.0
DU-13	4459+60	56' RT	4459+66	41' RT	16								0.0
DU-13	4459+66	40' RT	4459+84	0' RT	44								0.0
DU-13	4459+85	0' RT	4459+93	1' LT	8								2.7
DU-13	4459+84	0' RT	4459+84	5' LT	5								1.7
DU-13	4459+84	5' LT	4459+85	8' LT								0.1	0.0
DU-13	4460+15	40' RT	4460+15	49' RT	9								3.1
DU-13	4460+16	51' RT	4460+48	61' RT	34								11.6
DU-13	4460+16	50' RT	4460+50	51' RT		34							12.5
DU-13	4460+15	50' RT	4460+47	0' RT	60								20.5
DU-13	4460+38	2' LT	4460+47	0' RT	10								3.4
DU-13	4460+47	0' RT	4460+47	3' LT	3								1.0
DU-13	4460+48	4' LT	4460+51	5' LT	4								1.4

CTE | AECOM

DS-2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

DRAINAGE SCHEDULES

SCALE: NONE — DRAWN BY: NJH
DATE: June 9, 2006 — CHECKED BY: RMC

p:\p40466\civil\8-cntrs 18 & 19\sht\cntr 18d-drainage and utility plan\ds80022a.sht
6/15/2006 9:17:14 AM