

F.A.I. RTE. 90/94	SECTION •	COUNTY COOK	TOTAL SHEETS 312	SHEET NO. 86
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
60A62		• (1919.15, 2021-922 PT1 & PT2) R-1		

PIPE UNDERDRAINS

SHEET NUMBER	FROM		TO		PIPE UNDERDRAINS 6" (FEET)	PIPE UNDERDRAINS 6" SPECIAL (FEET)	CONNECTING STRUCTURE
	STATION	OFFSET	STATION	OFFSET			
DU-1	6056+38	8' RT	6059+94	8' RT	352	5	1-05
DU-1	6059+29	20' LT	6059+94	20' LT	372	5	1-04
DU-1	6059+94	8' RT	6061+95	8' RT	200	5	2-02
DU-1	6059+97	20' LT	6061+84	20' LT	188	5	2-01
DU-2	6061+95	8' RT	6063+26	8' RT	131	11	2-05
DU-2	6063+40	0'	6065+55	0'	215	9	3-01
DU-2	6061+86	20' LT	6063+38	20' LT	152	5	2-04
DU-2	6063+47	20' LT	6065+60	20' LT	213	5	3-09
DU-3	6065+72	20' LT	6066+43	20' LT	71		
DU-3	6066+43	20' LT	6066+53	21' LT	10		
DU-3	6066+53	21' LT	6068+46	21' LT	195	5	3-10
DU-3	6065+62	1' LT	6068+41	1' LT	279	10	3-07
DU-3	6067+55	6' RT	6067+55	19' LT		25	3-03
DU-3	6068+41	1' LT	6068+85	0' LT	37		
DU-3	6068+85	0'	6070+48	0'	163		
DU-3	6068+48	21' LT	6070+70	18' LT	226	5	EX
DU-4	6070+70	18' LT	6070+91	18' LT	20	5	EX
DU-4	6070+48	0'	6070+52	10'	11		
DU-4	6070+52	10' RT	6070+63	10' RT	11		
DU-4	6070+63	10' RT	6070+69	9' RT	6		
DU-4	6070+69	9' RT	6072+58	9' RT	188	5	4-04
DU-4	6072+63	4.5' RT	6072+61	16' RT	20		EX UD
DU-4	6072+58	9' RT	6073+20	9' RT	62		4-04
DU-4	4415+99	36' RT	4416+75	36' RT	74	13	4-06
DU-4	4416+75	36' RT	4417+42	33' RT	66		
DU-4	4417+42	33' RT	4417+59	43' RT	19		
DU-4	4417+59	43' RT	4417+84	48' RT	25		
DU-5	4417+84	48' RT	4419+42	48' RT	153		
DU-5	4419+78	59' RT	4419+42	49' RT	36	5	5-03
DU-5	4419+42	48' RT	4421+11	48' RT	156		5-03
DU-5	4421+11	48' RT	4421+00	50' RT			
DU-5	4421+11	50' RT	4421+98	47' RT	84		
DU-5	4421+98	47' RT	4422+12	47' RT	15		
DU-5	4422+07	38' RT	4423+05	38' RT	97	6	5-11
DU-6	4423+05	38' RT	4423+11	47' RT	11		
DU-6	4423+11	47' RT	4423+17	48' RT	6		
DU-6	4423+17	48' RT	4425+49	48' RT	232		
DU-6	4425+49	48' RT	4425+59	48.5' RT	10		
DU-6	4425+59	48.5' RT	4525+64	48' RT	5		
DU-6	4525+64	48' RT	4452+72	40' RT	11		
DU-6	4452+72	40' RT	4426+18	40' RT	46		
DU-6	4426+18	40' RT	4426+51	40' RT	33		
DU-6	4426+51	40' RT	4426+57	46' RT	9		
DU-6	4426+57	46' RT	4426+61	46' RT	3		
DU-6	4426+61	46' RT	4426+70	48' RT	9		
DU-6	4426+70	48' RT	4429+73	48' RT	303	5	7-04
DU-7	4429+73	48' RT	4432+42	48' RT	267		
DU-8	4432+42	48' RT	4433+50	41' RT	109	5	8-02
DU-8	4433+50	41' RT	4433+79	40' RT	28		8-02
DU-8	4436+46	13' LT	4437+14	12' LT	68	5	9-03
DU-9	4437+16	12' LT	4437+17	31' LT	41		EX UD
DU-9	4437+14	12' LT	4440+85	12' LT	371		9-03
DU-9	4440+85	12' LT	4443+33	12' LT	247	5	9-07
DU-9	4440+60	48' RT	4440+85	47' RT	25	5	9-06
DU-9	4440+85	47' RT	4441+06	46' RT	21		9-06
DU-9	4441+06	46' RT	4443+33	46' RT	227		
DU-10	4443+33	46' RT	4444+51	46' RT	119		
DU-10	4444+51	46' RT	4445+31	49' RT	81		
DU-10	4445+31	49' RT	4445+31	48' RT	1		
DU-10	4445+31	48' RT	4446+49	48' RT	118		
DU-10	4443+33	10' LT	4445+21	10' LT	188		
DU-10	4445+21	10' LT	4447+21	4' LT	199		
DU-11	4446+49	48' RT	4447+69	44' RT	120	5	11-01
DU-11	4447+21	4' LT	4447+31	2' LT	10		
DU-11	4447+31	2' LT	4447+61	2' LT	30	8	11-02
DU-11	4447+71	4.5' LT	4448+55	12' LT	84		
DU-11	4448+55	12' LT	4448+65	5' LT	12		
DU-11	4448+65	5' LT	4449+54	1' RT	89		
DU-11	4449+54	1' RT	4449+64	7' LT	13		
DU-11	4449+64	7' LT	4450+38	9' LT	74	5	11-09
DU-11	4447+69	44' RT	4448+55	41' RT	86		
DU-11	4448+55	41' RT	4448+65	32' RT	14		

PIPE UNDERDRAINS

SHEET NUMBER	FROM		TO		PIPE UNDERDRAINS 6" (FEET)	PIPE UNDERDRAINS 6" SPECIAL (FEET)	CONNECTING STRUCTURE
	STATION	OFFSET	STATION	OFFSET			
DU-11	4448+65	32' RT	4449+90	32' RT	125		
DU-11	4449+90	32' RT	4450+08	49' RT	25		
DU-11	4450+08	49' RT	4450+40	49' RT	32	5	11-06
DU-11	4450+40	46' RT	4450+40	5' LT	51	5	11-09
DU-11	4450+40	49' RT	4453+50	49' RT	310		11-06
DU-12	4453+50	49' RT	4455+59	49' RT	209	5	12-03
DU-12	4455+59	49' RT	4456+70	49' RT	111		
DU-13	4456+70	49' RT	4457+70	54' RT	100	5	13-01
DU-13	4457+70	54' RT	4460+42	68' RT	272		
DU-13	4460+42	68' RT	4460+81	68' RT	40		
DU-14	4460+81	68' RT	4460+81	71' RT	3		
DU-14	4460+81	71' RT	4461+00	71' RT	17	5	14-01
DU-14	4460+79	42' RT	4460+79	2' LT	77	8	14-04
DU-14	4461+00	71' RT	4461+99	70' RT	98		14-01
DU-14	4464+81	56' RT	4461+94	46' RT		13	14-12
DU-14	4461+94	46' RT	4463+08	46' RT	114		
DU-14	4463+13	46' RT	4464+27	47' RT	114	5	14-10
DU-14	4464+27	47' RT	4465+09	44' RT	83		
DU-14	4465+09	44' RT	4465+14	44' RT	5		
DU-14	4465+19	46' RT	4467+63	47' RT	244	5	14-13
DU-15	4467+63	47' RT	4468+19	47' RT	55		
DU-15	4468+19	47' RT	4468+77	48' RT	58		
DU-15	4468+77	48' RT	4471+07	48' RT	231	5	16-02
DU-16	4471+07	48' RT	4471+36	48' RT	29		
DU-16	4471+36	48' RT	4472+44	45' RT	108		
DU-16	4472+44	45' RT	4472+57	46' RT	12		
DU-16	4472+57	46' RT	4473+65	42' RT	109	5	16-06
DU-16	4473+65	42' RT	4473+84	42' RT	18		16-06
DU-16	4473+84	42' RT	4473+93	32' RT	14		
DU-16	4473+93	32' RT	4474+50	32' RT	57		
TOTALS					9,888	238	



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

DRAINAGE SCHEDULES

SCALE: NONE
 DATE: June 9, 2006

DRAWN BY: NJH
 CHECKED BY: RMC

DS-8

6/7/06 5:17:15 AM