

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1360	0101BR-2	COOK	90	4
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60A65

CODE #	PAY ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION CODE				
				J000-2A	X271-2A	Y002-1C	Y030-1E	Y031-1F
				ROADWAY	#016-0246 STRUCTURE	SIGNING	LIGHTING	TRAFFIC SIGNALS
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	88	88				
20101100	TREE TRUNK PROTECTION	EACH	7	7				
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	2	2				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1				
20200100	EARTH EXCAVATION	CU YD	202	202				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	55	55				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	129	129				
• 25000210	SEEDING CLASS 2A	ACRE	0.1	0.1				
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3				
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3				
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3				
• 25100630	EROSION CONTROL BLANKET	SQ YD	129	129				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3	3				
28000510	INLET FILTERS	EACH	6	6				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	500	500				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	116	116				
42000531	PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2" (JOINTED)	SQ YD	149	149				
42001300	PROTECTIVE COAT	SQ YD	1,857	770	1,087			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	380	380				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,625	1,625				
42400800	DETECTABLE WARNINGS	SQ FT	48	48				
44000100	PAVEMENT REMOVAL	SQ YD	76	76				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	628	628				
44000600	SIDEWALK REMOVAL	SQ FT	1,990	1,990				
44000700	APPROACH SLAB REMOVAL	SQ YD	522	522				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	17	17				
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	161	161				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1				
50102400	CONCRETE REMOVAL	CU YD	23.4	23.4				
50300225	CONCRETE STRUCTURES	CU YD	65.9	65.9				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	288.1	288.1				
50300260	BRIDGE DECK GROOVING	SQ YD	716	716				
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20	20				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1				
50500505	STUD SHEAR CONNECTORS	EACH	4,260	4,260				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	73,370	73,370				
50900805	PEDESTRIAN RAILING	FOOT	435	435				
51500100	NAME PLATES	EACH	1	1				
58700200	BRIDGE SEAT SEALER	SQ FT	320	320				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	4				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	285	285				

• SPECIALTY ITEM



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. ROUTE 1360 (FOSTER AVENUE)

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: JUNE 30, 2006

DRAWN BY: NEC
CHECKED BY: SPF

6/30/2006 8:40:39 AM K:\182519\Cocci\Design\8259_SumQty_Cls.dgn