

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1360	0101BR-2	COOK	90	5
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 60A65				

CODE #	PAY ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION CODE				
				J000-2A ROADWAY	X271-2A #016-0246 STRUCTURE	Y002-10 SIGNING	Y030-1E LIGHTING	Y031-FF TRAFFIC SIGNALS
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	148	148				
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	189	189				
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50	50				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1				
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	124	124				
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	137	137				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	556	556				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	198	198				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	36	36				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	446	446				
72000100	SIGN PANEL - TYPE 1	SQ FT	74		74			
72000200	SIGN PANEL - TYPE 2	SQ FT	44		44			
72000300	SIGN PANEL - TYPE 3	SQ FT	621		621			
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	74		74			
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	44		44			
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	621		621			
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2		2			
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	319		319			
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,020		1,020			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30		30			
72900200	METAL POST - TYPE B	FOOT	12		12			
73000100	WOOD SIGN SUPPORT	FOOT	34		34			
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	97.2	97.2				
73400100	CONCRETE FOUNDATIONS	CU. YD.	38		38			
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	7		7			
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	155	155				
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,094	2,094				
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	658	658				
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	80	80				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35				
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	19	19				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	489	489				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	23	23				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1		
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1		
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	6			6		
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	2			2		
81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16"x14"x6"	EACH	1			1		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	490			490		
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO.10	FOOT	1,500			1,500		

* SPECIALTY ITEM



Excellence through Ownership
200 West Front Street
Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. ROUTE 1360 (FOSTER AVENUE)

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: JUNE 30, 2006

DRAWN BY: NEC
CHECKED BY: SFP

Rev.