

CODE #	PAY ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION CODE				
				J000-2A ROADWAY	X271-2A #016-0246 STRUCTURE	Y002-1C SIGNING	Y030-1E LIGHTING	Y031-1F TRAFFIC SIGNALS
81700115	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO.8	FOOT	1,750				1,750	
81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO.6	FOOT	3,200				3,200	
81800630	AERIAL CABLE, 2-1/C NO. 6, ALUMINUM, WITH MESSENGER WIRE	FOOT	375				375	
82106400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT (INSTALL ONLY)	EACH	11				11	
82107110	UNDERPASS LUMINAIRE, 70W, HIGH PRESSURE SODIUM, STAINLESS STEEL HOUSING	EACH	8				8	
XX004947	LIGHT POLE FOUNDATION, 24" DIAMETER	EACH	5				5	
89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM	1					1
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	112				112	
A2004816	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	15	15				
XX002113	TEMPORARY LIGHTING CONTROLLER	EACH	1				1	
XX004812	VIDEO TAPING OF SEWERS	FOOT	400	400				
XX005369	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
X0325541	REMOVE EXISTING LIGHTING SYSTEM	L SUM	1				1	
X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	28				28	
X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SQ YD	64	64				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	151		151			
X0324183	CLEAN EXISTING ELECTRICAL MANHOLE OR HANDHOLE	EACH	2				2	
X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	464		464			
X0325015	ADJUST FRAME AND LID	EACH	4				2	2
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	797		797			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	113	113				
X4409400	BITUMINOUS SURFACE REMOVAL 1 3/4"	SQ YD	1,149	1,149				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	5	5				
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	2			2		
X8110145	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., RIGID GALV., PVC COATED	FOOT	400				400	
X8110155	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., RIGID GALVANIZED STEEL, PVC COATED	FOOT	965				965	
X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	13				13	
Z0002600	BAR SPLICERS	EACH	124		124			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	8				8	
Z0076600	TRAINEES	HOUR	500	500				
Z0064800	SELECTIVE CLEARING	UNIT	5	5				
X0325527	REMOVE AND REINSTALL SIGNAL EQUIPMENT	L SUM	1					1
X0325528	REMOVE AND REINSTALL LIGHTING EQUIPMENT	L SUM	1				1	
X0325529	LIGHT POLE, ALUMINUM, ARTERIAL, DAVIT, 15" BOLT CIRCLE (INSTALL ONLY)	EACH	5				5	
X0325530	MAST ARM, ALUMINUM, ARTERIAL, DAVIT, 8' (INSTALL ONLY)	EACH	5				5	
X0325531	CONDUIT IN TRENCH, 2" PVC SCHEDULE 40	FOOT	170				170	
X0325532	CONDUIT IN TRENCH, 2" PVC SCHEDULE 80	FOOT	345				345	
X0325533	REVLAC SIGN REMOVAL	L SUM	1			1		
X0325534	REVLAC SIGN RE-INSTALLATION	L SUM	1			1		

* SPECIALTY ITEM
 A Y080

rjngroup
 Excellence through Ownership
 200 West Front Street
 Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 1360 (FOSTER AVENUE)

SUMMARY OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE: JUNE 30, 2006

DRAWN BY: NEC
 CHECKED BY: SPF

6/30/2006 9:25:17 AM K:\MS2519\0006\Design\2519_SumQty_03.dgn

Rev.