

CURB & GUTTER				
LOCATION	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE B-9.12 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER TYPE M-2.12 (FOOT)	PROTECTIVE COAT (SQ YD)
EASTBOUND				
STA. 98+96.00 TO 99+29.75	52			11
STA. 99+29.75 TO 99+42.00		12		3
STA. 100+58.00 TO 101+10.75		53		7
STA. 101+10.75 TO 102+50.00	181			64
WESTBOUND				
STA. 98+96.00 TO 99+29.75	52			11
STA. 99+29.75 TO 99+42.00		12		3
STA. 100+58.00 TO 101+28.04		71		7
STA. 101+28.04 TO 103+16.64			189	55
TOTAL	285	148	189	161


REMOVAL SCHEDULE						
LOCATION	PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB & GUTTER REMOVAL (FOOT)	SIDEWALK REMOVAL (SQ FT)	APPROACH SLAB REMOVAL (SQ YD)	GUARDRAIL REMOVAL (FOOT)	BITUMINOUS SURFACE REMOVAL (SQ YD)
EASTBOUND						
STA. 98+90.00 TO 99+42.00	37	67	392	133		35
STA. 100+58.00 TO 102+50		236	675	126		477
WESTBOUND						
STA. 98+90.00 TO 99+42.00	39	66	430	136		35
STA. 100+58.00 TO 103+16.64		259	493	127	124	602
TOTAL	76	628	1,990	522	124	1,149

PAVEMENT MARKING SCHEDULE									
LOCATION	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING LINE 6" (FOOT)	TEMPORARY PAVEMENT MARKING LINE 24" (FOOT)	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS (SQ FT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 4" (FOOT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 6" (FOOT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 24" (FOOT)	PAVMENT MARKING REMOVAL (SQ FT)
FOSTER AVENUE									
EASTBOUND									
STA. 97+17.00 TO 98+17.00		100		73		24			8
STA. 98+96.00 TO 102+50.00						443			
CENTERLINE & TURN LANE									
STA. 99+11.00 TO 101+31.00					77		220		
STA. 101+65.00 TO 102+50.00						172			
PEDESTRIAN WALKWAY									
STA. 99+00.00 TO 99+06.00							167		
STA. 99+09.00 TO 99+11.00								42	
INTERSECTION									
STA. 98+29.00 TO 98+96.00		20				459			
WESTBOUND									
STA. 98+96.00 TO 102+50.00						48			
CICERO AVENUE									
NORTHBOUND									
STA. 17+53.00 TO 19+53.00	48		36	28				38	146
STA. 20+43.00 TO 22.78.00									
CENTERLINE & TURN LANES									
STA. 17+53.00 TO 19+53.00	400				39	400	126		174
STA. 20+43.00 TO 22.78.00					39		145		39
SOUTHBOUND									
STA. 17+53.00 TO 19+53.00	48	70				48			29
STA. 20+43.00 TO 22.78.00	60	8		36		60			93
TOTAL	556	198	36	137	155	2,094	658	80	489

PAVEMENT SCHEDULE								
LOCATION	SUB-BASE GRANULAR MATERIAL TYPE B 4" (CU YD)	PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2" (JOINTED) (SQ YD)	PROTECTIVE COAT (SQ YD)	BRIDGE APPROACH PAVEMENT (SPECIAL) (SQ YD)	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SQ FT)	BITUMINOUS SHOULDERS SUPERPAVE 8" (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL (SQ YD)	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX "D", N50 (TON)
EASTBOUND								
STA. 98+90.00 TO 99+42.00	123	74.5	141	95	378			3.5
STA. 100+58.00 TO 102+50.00	56		141	95	503		32	59
WESTBOUND								
STA. 98+96.00 TO 99+42.00	123	74.5	141	95	405			3.5
STA. 100+58.00 TO 103+16.64	198		186	95	339	161	32	47
TOTAL	500	149.0	609	380	1,625	161	64	113

GUARDRAIL SCHEDULE			
LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT) (EACH)
WESTBOUND			
STA. 101+08.25 TO 101+41.40		1	
STA. 101+41.40 TO 101+91.40	50		
STA. 101+91.40 TO 102+41.40			1
TOTAL	50	1	1

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EARTHWORK BALANCE (+) WASTE (-) SHORTAGE (CU YD)	FURNISHED EXVACATION (CU YD)
STA. 98+96.00 TO STA. 99+42.00	77.6	1.0	1.5	58.2	(+) 56.7	0
STA. 100+58.00 TO STA. 103+16.64	124.3	53.3	6.3	93.3	(+) 87.0	0

 Excellence through Ownership 200 West Front Street Wheaton, IL 60187	REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.U. ROUTE 1360 (FOSTER AVENUE) SCHEDULE OF QUANTITIES SCALE: VERT. HORIZ. DATE: JUNE 30, 2006 DRAWN BY: NEC CHECKED BY: SPF
	NAME	DATE	