

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-031 BY	WILL	137	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN
100% STATE
CSXRR SUNNYLAND DRAIN
099-0312 099-0014
~~X171-50~~ X020-2A
099-0015

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	099-0312	099-0014	099-0015
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	9	9			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	34	34			
20200100	EARTH EXCAVATION	CU YD	5971	5971			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7669	7669			
20400800	FURNISHED EXCAVATION	CU YD	7852	7852			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	198		95		103
20800150	TRENCH BACKFILL	CU YD	17	17			
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	21483	21483			
25000210	SEEDING, CLASS 2A	ACRE	4.44	4.44			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	394	394			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	394	394			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	394	394			
25100115	MULCH, METHOD 2	ACRE	4.69	4.69			
25100630	EROSION CONTROL BLANKET	SQ YD	21483	21483			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	469	469			
28000300	TEMPORARY DITCH CHECKS	EACH	6	6			
28000510	INLET FILTERS	EACH	7	7			
28100107	STONE RIPRAP, CLASS A4	SQ YD	8	8			
28200200	FILTER FABRIC	SQ YD	8	8			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5			
40600895	CONSTRUCTING TEST STRIP	EACH	3	3			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	420	420			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	267	267			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	95	95			
42100320	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11"	SQ YD	5171	5171			
42100920	PAVEMENT REINFORCEMENT 11"	SQ YD	5171	5171			
42101300	PROTECTIVE COAT	SQ YD	6030	6030			
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	766	766			
44000700	APPROACH SLAB REMOVAL	SQ YD	441	441			
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	1360	1360			
44004000	PAVED DITCH REMOVAL	FOOT	192	192			
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	962	962			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	67	67			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	153	153			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	111	111			
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	1928	1928			
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	6982	6982			
48301000	PROTECTIVE COAT	SQ YD	6982	6982			
50102400	CONCRETE REMOVAL	CU YD	50.6		6.6		44.0
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3.0			
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1.0		1.0		
50105220	PIPE CULVERT REMOVAL	FOOT	163	163			
50200100	STRUCTURE EXCAVATION	CU YD	344		252.0		92.0
50200300	COFFERDAM EXCAVATION	CU YD	20				20.0
50200500	COFFERDAMS	EACH	2				2.0
50300100	FLOOR DRAINS	EACH	14		12.0		2.0

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (OVER CSX RR AND SUNNYLAND DRAIN)
BRIDGE WIDENING

SUMMARY OF QUANTITIES
I

SCALE: N.T.S. DRAWN BY AG
DATE: 07/21/06 CHECKED BY DDH

TENG TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS-PLANNERS
CHICAGO, ILLINOIS

PLT DATE = 08/01/06
FILE NAME = 60B85.DWG
USER NAME = JWB
7-19-2006 13:45:51
S:\DOCUMENT\02361501\CIVIL\CON\SUPP\14001.SHT

Rev