CONTRACT NO. 60B85

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-031 BY	WILL	137	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	CSXRR 099-0312 XT1-5B	SUNNYLAND DRAIN 099-0014 099-0015 X020-2A
					URBAN 100% STATE	
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	23.5			23.5
50300225	CONCRETE STRUCTURES	CU YD	181.7		156.5	25.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	430.5		395.4	35.1
50300260	BRIDGE DECK GROOVING	SQ YD	1455		1389	66
50300300	PROTECTIVE COAT	SQ YD	1959		1585	374
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	110		110	
50500505	STUD SHEAR CONNECTORS	EACH	3192		3192	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	118990		108420	10570
51100100	SLOPE WALL 4 INCH	SQ YD	341		341	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	622		622	
51201710	FURNISHING STEEL PILES HP12X84	FOOT	46		46	
51202700	DRIVING STEEL PILES	FOOT	668		668	
51203400	TEST PILE STEEL HP10X42	EACH	3		3	
51203710	TEST PILE STEEL HP12X84	EACH	1		1	
51204600	METAL SHOES	EACH	15		15	
51500100	NAME PLATES	EACH	3		1	2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	1	1		
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	1	1		
54246205	INLET BOX, STANDARD 542526	EACH	1	1		
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	3	3		
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	217	217		
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	201	201		
55020500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 48"	FOOT	51	51		
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15	FOOT	11	11		
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	170	170		
55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42	FOOT	543	543		
55100500	STORM SEWER REMOVAL 12"	FOOT	13	13		
55101600	STORM SEWER REMOVAL 36"	FOOT	552	552		
59000100	EPOXY CRACK SEALING	FOOT	10			10
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	98		52	46
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	16	16		
60107700	PIPE UNDERDRAINS 6"	FOOT	5747	5747		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	344	344		
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	195		195	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	4	4		
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	3	3		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2		
60500040	REMOVING MANHOLES	EACH	3	3		
60615400	PAVED DITCH, TYPE A-15	FOOT	192	192		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	338	338		
* 63001305	FURNISHING AND INSTALLING RAIL ELEMENT PLATES	EACH	57	57		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		

* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (OVER CSX RR AND SUNNYLAND DRAIN)
BRIDGE WIDENING

SUMMARY OF QUANTITIES II

SCALE: N.T.S. DRAWN BY AG
DATE 07/21/06 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$

7-27-2006,11:57:24 SHJZEKJ S:\DOCUMENT\22061587\CIVIL\DGN\SQ091A02.SHT