

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-031 BY	WILL	137	8C
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTINUED FROM THE PREVIOUS COLUMN

PAVEMENT MARKING TAPE, TYPE III 4"										TOTAL	39,998.00	FOOT
DIRECTION ON I-55	FROM STA.	TO STA.	LINE WIDTH	LINE TYPE	LENGTH FEET	LINE WIDTH	Z OF T	COLOR	Sub totals			
STAGE I												
I-55												
N.B.	157+23.64	198+03.42	4"	SOLID	4,079.78	0.333	1	YELLOW	4,079.78			
N.B.	158+33.67	191+87.12	4"	SOLID	3,353.45	0.333	1	WHITE	3,353.45			
N.B.	190+06.93	191+87.95	4"	SOLID	181.02	0.333	1	WHITE	181.02			
N.B.	190+06.93	196+35.41	4"	SOLID	628.48	0.333	1	WHITE	628.48			
N.B.	484+47.75	499+44.25	4"	SOLID	1,496.50	0.333	1	YELLOW	1,496.50			
N.B.	485+50.40	498+74.44	4"	SOLID	1,324.04	0.333	1	WHITE	1,324.04			
S.B.	137+05.07	199+60.40	4"	SOLID	6,255.33	0.333	1	YELLOW	6,255.33			
S.B.	138+15.27	194+86.17	4"	SOLID	5,670.90	0.333	1	WHITE	5,670.90			
S.B.	193+52.08	194+89.04	4"	SOLID	137.80	0.333	1	WHITE	137.80			
S.B.	193+52.08	198+57.52	4"	SOLID	505.44	0.333	1	WHITE	505.44			
S.B.	185+80.24	193+51.85	4"	SKIP-DASH	771.61	0.333	0.25	WHITE	192.90			
S.B.	484+47.75	499+44.25	4"	SOLID	1,496.50	0.333	1	YELLOW	1,496.50			
S.B.	485+01.65	497+57.01	4"	SOLID	1,255.36	0.333	1	WHITE	1,255.36			
STAGE II												
I-55												
S.B.	137+05.07	199+61.00	4"	SOLID	6,255.93	0.33	1	YELLOW	6,255.93			
S.B.	137+05.07	194+49.15	4"	SOLID	5,744.08	0.33	1	WHITE	5,744.08			
S.B.	190+74.92	194+51.29	4"	SOLID	376.37	0.33	1	WHITE	376.37			
S.B.	190+74.92	199+61.00	4"	SOLID	886.08	0.33	1	WHITE	886.08			
S.B.	184+42.00	190+75.00	4"	SKIP-DASH	633.00	0.333	1	WHITE	158.25			

PAVEMENT MARKING TAPE, TYPE III 5"										TOTAL	4,786.00	FOOT
DIRECTION ON I-55	FROM STA.	TO STA.	LINE WIDTH	LINE TYPE	LENGTH FEET	LINE WIDTH	Z OF T	COLOR	Sub totals			
STAGE I												
N.B.	157+78.55	197+19.42	5"	SKIP DASH	3940.87	0.41666	0.25	WHITE	985.22			
S.B.	137+59.97	199+15.17	5"	SKIP DASH	6155.2	0.41666	0.25	WHITE	1,538.80			
N.B.	484+98.67	499+04.95	5"	SKIP DASH	1406.28	0.41666	0.25	WHITE	351.57			
S.B.	484+65.45	498+50.44	5"	SKIP DASH	1384.99	0.41666	0.25	WHITE	346.25			
STAGE II												
S.B.	137+05.07	199+61.00	5"	SKIP DASH	6255.93	0.41666	0.25	WHITE	1,563.98			

WORK ZONE PAVEMENT MARKING REMOVAL										TOTAL	15,313	SQ FT
DIRECTION	FROM STA.	TO STA.	LINE WIDTH	LINE TYPE	LENGTH FEET	LINE WIDTH	Z OF T	COLOR	Sub totals			
REMOVAL of 5" PAVEMENT MARKING from STAGE I												
N.B.	157+78.55	197+19.42	5	SKIP DASH	3940.87	0.417	0.25	WHITE	410.51			
S.B.	137+59.97	199+15.17	5	SKIP DASH	6155.2	0.417	0.25	WHITE	641.17			
N.B.	484+98.67	499+04.95	5	SKIP DASH	1406.28	0.417	0.25	WHITE	146.49			
S.B.	484+65.45	498+50.44	5	SKIP DASH	1384.99	0.417	0.25	WHITE	144.27			
REMOVAL of 5" PAVEMENT MARKING from STAGE II												
S.B.	137+05.07	199+61.00	5	SKIP DASH	6255.93	0.417	0.25	WHITE	651.66			
REMOVAL of 4" PAVEMENT MARKING from STAGE I												
S.B.	185+80.24	193+51.85	4"	SKIP-DASH	771.61	0.333	0.25	WHITE	64.24			
N.B.	157+23.64	198+03.42	4"	SOLID	4,079.78	0.333	1	YELLOW	358.57			
N.B.	158+33.67	191+87.12	4"	SOLID	3,353.45	0.333	1	WHITE	116.70			
N.B.	190+06.93	191+87.95	4"	SOLID	181.02	0.333	1	WHITE	60.28			
N.B.	190+06.93	196+35.41	4"	SOLID	628.48	0.333	1	WHITE	209.28			
N.B.	484+47.75	499+44.25	4"	SOLID	1,496.50	0.333	1	YELLOW	498.33			
N.B.	485+50.40	498+74.44	4"	SOLID	1,324.04	0.333	1	WHITE	440.91			
S.B.	137+05.07	199+60.40	4"	SOLID	6,255.33	0.333	1	YELLOW	2083.02			
S.B.	138+15.27	194+86.17	4"	SOLID	5,670.90	0.333	1	WHITE	1888.41			
S.B.	193+52.08	194+89.04	4"	SOLID	137.80	0.333	1	WHITE	45.89			
S.B.	193+52.08	198+57.52	4"	SOLID	505.44	0.333	1	WHITE	168.31			
S.B.	484+47.75	499+44.25	4"	SOLID	1,496.50	0.333	1	YELLOW	498.33			
S.B.	485+01.65	497+57.01	4"	SOLID	1,255.36	0.333	1	WHITE	418.03			
REMOVAL of 4" PAVEMENT MARKING from STAGE II												
S.B.	184+42.00	190+75.00	4"	SKIP-DASH	633.00	0.333	0.25	WHITE	52.70			

CONTINUED IN THE NEXT COLUMN

DIRECTION	FROM STA.	TO STA.	LINE WIDTH	LINE TYPE	LENGTH FEET	LINE WIDTH	Z OF T	COLOR	Sub totals
S.B.	137+05.07	199+61.00	4"	SOLID	6,255.93	0.33	1	YELLOW	2083.22
S.B.	137+05.07	194+49.15	4"	SOLID	5,744.08	0.33	1	WHITE	1912.78
S.B.	190+74.92	194+51.29	4"	SOLID	376.37	0.33	1	WHITE	125.33
S.B.	190+74.92	199+61.00	4"	SOLID	886.08	0.33	1	WHITE	295.06

TEMPORARY CONCRETE BARRIER							TOTAL	7488	FOOT
LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	LENGTH FEET			Sub totals	
STAGE I									
I-55 S.B.	142+00.00		187+27.00		4,527.00			4,527.00	
I-55 S.B.	489+43.00		493+47.00		404.00			404.00	
I-55 N.B.	165+58.00		187+38.00		2,180.00			2,180.00	
I-55 N.B.	490+72.00		494+49.00		377.00			377.00	

RELOCATE TEMPORARY CONCRETE BARRIER							TOTAL	467	FOOT
LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	LENGTH FEET			Sub totals	
SB BASELINE									
I-55 S.B.	166+16.00		170+83.00		467.00			467.00	

THERMOPLASTIC PAVEMENT MARKING - LINE 4"										TOTAL	12,921.00	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH FEET	LINE TYPE	LINE COLOR	%		Sub totals				
SB	135+05.07	144+63.00	957.93	SOLID	WHITE	1		957.93				
SB	135+05.07	144+75.00	969.93	SOLID	YELLOW	1		969.93				
SB	186+03.00	195+83.00	980.00	SOLID	WHITE	1		980.00				
SB	194+51.00	195+83.00	132.00	SOLID	YELLOW	1		132.00				
SB	194+51.00	199+61.00	510.00	SOLID	WHITE	1		510.00				
SB	186+03.00	199+61.00	1,358.00	SOLID	YELLOW	1		1,358.00				
NB	187+28.00	191+87.00	459.00	SOLID	WHITE	1		459.00				
NB	193+08.00	198+03.00	495.00	SOLID	WHITE	1		495.00				
NB	187+28.00	198+03.00	1,075.00	SOLID	YELLOW	1		1,075.00				
SB	484+48.00	499+44.00	1,496.00	SOLID	WHITE	1		1,496.00				
SB	484+48.00	499+44.00	1,496.00	SOLID	YELLOW	1		1,496.00				
NB	484+48.00	499+44.00	1,496.00	SOLID	WHITE	1		1,496.00				
NB	484+48.00	499+44.00	1,496.00	SOLID	YELLOW	1		1,496.00				

THERMOPLASTIC PAVEMENT MARKING - LINE 8"								TOTAL	1742	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH FEET	LINE COLOR				Sub totals		
I-55 SB	190+14.00	194+51.00	437.0	WHITE				437.0		
I-55 SB	190+14.00	194+51.00	437.0	WHITE				437.0		
I-55 NB	188+74.00	193+08.00	434.0	WHITE				434.0		
I-55 NB	188+74.00	193+08.00	434.0	WHITE				434.0		

THERMOPLASTIC PAVEMENT MARKING - LINE 12"										TOTAL	466.0	FOOT
LOCATION	FROM STA.	TO STA.	DISTANCE	SPACING 500' SHLD. 30'-GORE*OF LINES	MEASURE LENGTH FEET	LINE COLOR	Sub totals					
I-55 SB	135+05.07	144+63.00	957.9	1.0	9.00	WHITE	9.0					
I-55 SB	186+03.00	195+83.00	980.0	1.0	8.70	WHITE	8.7					
I-55 SB	190+14.00	194+51.00	437.0	1.0	107.17	WHITE	107.2					
I-55 SB	194+51.00	199+61.00	510.0	1.0	18.80	WHITE	18.8					
I-55 NB	188+74.00	193+08.00	434.0	1.0	215.24	WHITE	215.2					
I-55 NB	193+08.00	198+03.00	495.0	1.0	19.00	WHITE	19.0					
I-55 SB	484+48.00	499+44.00	1496.0	1.0	39.40	WHITE	39.4					
I-55 NB	484+48.00	499+44.00	1496.0	1.0	48.30	WHITE	48.3					

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"								TOTAL	103	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH	25%				Sub totals		
DOTTED LINES for AUXILLARY LANES 6' - SKIP 2' - DASH										
S.B.	186+03.00	190+14.00	411.00	25%	0.25			102.75		

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"										TOTAL	1,596.0	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH	ADJ. FACTOR				Sub totals				
LANE LINES - 10' DASH 30' SKIP												
S.B.	135+05.07	144+63.00	957.9	25%	0.25			239.5				
N.B.	187+28.00	198+03.00	1,075.0	25%	0.25			268.8				
S.B.	186+03.00	199+61.00	1,358.0	25%	0.25			339.5				
N.B.	484+48.00	499+44.00	1,496.0	25%	0.25			374.0				
S.B.	484+48.00	499+44.00	1,496.0	25%	0.25			374.0				

POLYUREA PAVEMENT MARKING TYPE I - LINE 4"										TOTAL	14,505.00	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH FT	LINE TYPE	LINE COLOR	%		Sub totals				
S.B.	144+63.00	186+03.00	4,140.00	SOLID	WHITE	100		4,140.00				
S.B.	144+75.00	186+03.00	4,128.00	SOLID	YELLOW	100		4,128.00				
S.B.	182+41.00	186+03.00	362.00	SKIP DASH	WHITE	0.25		90.50				
N.B.	156+55.00	187+28.00	3,073.00	SOLID	WHITE	100		3				