CONTRACT NO. 60B85

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-031 BY	WILL	137	54
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE
1001	SS 1 RCP CL 2 48	DIA 48"	51	0.12	17.2		1002	1001
1003	SS 2 RCP CL 3 42	DIA 42"	414	0.07	--		1006	ES
1004	SS 2 RCP CL 3 42	DIA 42"	129	0.07	--		ES	1006
1005	SS 2 RCP CL 3 15	DIA 15"	11	0.40	--		1005	ES
1006	SS 1 RCP CL 4 15	DIA 15"	3	0.40	--		1007	1006
1010	SS 1 RCP CL 4 24	DIA 24"	22	0.60	--		1009	1010
1011	SS 1 RCP CL 4 24	DIA 24"	170	0.60	--		1011	1009
1012	SS 1 RCP CL 4 18	DIA 18"	171	1.50	--		1012	1011
1013	SS 1 RCP CL 4 18	DIA 18"	46	2.00	--		1013	1012
1801	SS 1 RCP CL 4 24	DIA 24"	8	1.00	--		1801	1802
1802	SS 2 RCP CL 3 24	DIA 24"	170	1.96	--		1802	1850

PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE

LEGEND

ES - EXISTING STRUCTURE
EP - EXISTING PIPE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (OVER CSX RR AND SUNNYLAND DRAIN)
BRIDGE WIDENING

DRAINAGE SCHEDULE - II
PROPOSED PIPES

SCALE:
DRAWN BY SN
DATE 07/07/06
CHECKED BY TKL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

-:\DJ0P01A01.DGN,-\BD79\P020L.DGN,-\DJ0P01A02.DGN,-\DJ0P01A03.DGN
7-07-2006, 9:30:35 DMGC1P2Z S:\DOCUMENT\BESMER\CIVIL\DGN\DJ0P01A11.SHT