

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
	50Q-03	OF	8	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% STATE	ROADWAY	US 30	EJ&E SB	EJ&E NB	MINK	RENWICK	MS	LILLY CACHE	RTE 126	LIGHTING
				Sta. 573+00.00 to Sta. 789+00.00	Sta. 587+80.82	Sta. 608+37.25	Sta. 608+37.25	Sta. 630+09.46	Sta. 631+48.98	Sta. 710+34.50	Sta. 773+45.67	Sta. 781+12.54	Sta. 573+00.00 to Sta. 789+00.00
				1000-2A	X231-2A	X171-5B	X171-5B	X020-2A	SFTY-2A	X131-2A	X020-2A	SFTY-2A	Y030-1E
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	412,010		174,540	97,620	35,320	38,930	500	64,710		310	
51100100	SLOPE WALL 4 INCH	SQ YD	181		181								
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	399			217	182						
51201000	FURNISHING METAL PILE SHELLS 12"	FOOT	288							288			
51201400	FURNISHING STEEL PILES HP10X42	FOOT	2,885			1,832	678	375					
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,234		1,234								
51202600	DRIVING AND FILLING SHELLS	FOOT	288							288			
51202700	DRIVING STEEL PILES	FOOT	4,119		1,234	1,832	678	375					
51203200	TEST PILE METAL SHELLS	EACH	2							2			
51203400	TEST PILE STEEL HP10X42	EACH	8			2	2	4					
51203600	TEST PILE STEEL HP12X53	EACH	5		5								
51204600	METAL SHOES	EACH	127		39	54	22	12					
51205200	TEMPORARY SHEET PILING	SQ FT	8,553			700	258	422		3,016	4,157		
51500100	NAME PLATES	EACH	9		2	1	1	2		2	1		
54001000	BOX CULVERT END SECTIONS	EACH	2								2		
54011206	PRECAST CONCRETE BOX CULVERT 12' X 6'	FOOT	372								372		
54011207	PRECAST CONCRETE BOX CULVERT 12' X 7'	FOOT	186								186		
54200427	PIPE CULVERTS, TYPE 1 RCCP 12"	FOOT	37	37									
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	3									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3									
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	1	1									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1									
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3									
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	1	1									
54216950	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 18" RISER	EACH	1	1									
54216960	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 18" RISER	EACH	1	1									
54246405	INLET BOX, STANDARD 542531	EACH	3	3									
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2									
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1									
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	3	3									
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	1	1									
54248515	CONCRETE COLLAR	EACH	4	4									
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	484	484									
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	303	303									

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO LILLY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 07-21-06

DRAWN BY AR
 CHECKED BY SJV

