

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	7
STA. TO STA.				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		500-04	OF 8	

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% STATE	CONSTRUCTION TYPE CODE																	
				ROADWAY Sta. 573+00.00 to Sta. 789+00.00 1000-2A	US 30 Sta. 587+80.82 X231-2A	EJ&E SB Sta. 608+37.25 X171-5B	EJ&E NB Sta. 608+37.25 X171-5B	MINK Sta. 630+09.46 X020-2A	RENWICK Sta. 631+48.98 SFTY-2A	MS Sta. 710+34.50 X131-2A	LILLY CACHE Sta. 773+45.67 X020-2A	RTE 126 Sta. 781+12.54 SFTY-2A	LIGHTING Sta. 573+00.00 to Sta. 789+00.00 Y030ME								
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	197	197																	
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	247	247																	
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	174	174																	
55020100	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	65	65																	
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	2,537	2,537																	
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	2,430	2,430																	
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	2,955	2,955																	
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21"	FOOT	1,527	1,527																	
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	773	773																	
55022100	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 27"	FOOT	326	326																	
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	160	160																	
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	125	125																	
55035400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	30	30																	
55035600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	643	643																	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,140	1,140																	
55100500	STORM SEWER REMOVAL 12"	FOOT	37	37																	
55100700	STORM SEWER REMOVAL 15"	FOOT	103	103																	
55100900	STORM SEWER REMOVAL 18"	FOOT	323	323																	
55101200	STORM SEWER REMOVAL 24"	FOOT	163	163																	
55101400	STORM SEWER REMOVAL 30"	FOOT	82	82																	
542JA036	PIPE CULVERTS, CLASS A 36" (JACKED)	FOOT	160	160																	
58700200	BRIDGE SEAT SEALER	SQ FT	510		148	161	70				131										
59000100	EPOXY CRACK SEALING	FOOT	129		60	37	8	13	8				3								
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	161		36	47	25	20		33											
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4																	
60107700	PIPE UNDERDRAINS 6"	FOOT	20,593	20,593																	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	384	384																	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	393		90	90	42	73		98											
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1																	
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	73	73																	
60201320	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	3	3																	
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	21	21																	
60205020	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	3	3																	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																	

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 07-21-06

DRAWN BY AR
CHECKED BY SJV

