CONTRACT NO. 60B86

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		SOQ-07 OF 8		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (100% STATE URBAN)	CONSTRUCTION TYPE CODE: ROADWAY Sta. 573+00.00 to Sta. 789+00.00 I000-2A	US 30 Sta. 587+80.82 X231-2A	EJ&E SB Sta. 608+37.25 X171-5B	EJ&E NB Sta. 608+37.25 X171-5B	MINK Sta. 630+09.46 X020-2A	RENWICK Sta. 631+48.98 SFTY-2A	MS Sta. 710+34.50 X131-2A	LILLY CACHE Sta. 773+45.67 X020-2A	RTE 126 Sta. 781+12.54 SFTY-2A	LIGHTING Sta. 573+00.00 to Sta. 789+00.00 Y030-1E
* 82107110	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	6										6
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	18										18
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	2										2
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	12										12
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	2										2
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2										2
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	7,899	7,899									
X0320870	BRACED EXCAVATION	CU YD	92		92								
X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SQ YD	359			92	84	40		143			
* X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1										1
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	1	1									
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1,540	1,540									
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5									
X0322729	MATERIAL TRANSFER DEVICE	TON	28,215	28,215									
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	1				1						
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	16	16									
X0323443	PRECAST MODULAR RETAINING WALL	SQ FT	368			368							
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	349			71	67			211.5			
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	371		233	71	67						
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	27		24	1				2			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	8,315	8,315									
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	2,000	2,000									
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	249		78	112	59						
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	7	7									
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2									
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SY YD	2,003	2,003									
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	823	823									
X0484300	MEDIAN INLET BOX REMOVAL	EACH	2	2									
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	15,468	15,468									
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	959	959									
X4066570	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	14,108	14,108									
X4066680	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	14,108	14,108									
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1					1					
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1					1					

* SPECIALTY ITEMS

Rev.

PARSONS BRINCKERHOFF

REVISIONS	
NAME	DATE
S. VERTHEIN	08/01/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

SUMMARY OF QUANTITIES

SCALE:
DATE: 07-21-06
DRAWN BY
CHECKED BY

FINAL