CONTRACT NO. 60B86

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	192
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE
2705	SS 1 RCP CL 4 24	DIA 24"	12	0.99	0.7		2705	2706
2706	SS 1 RCEP S30 R19	SPAN 30", RISE 19"	125	0.30	9.7		2706	2707
2707	SS 2 RCEP S30 R19	SPAN 30", RISE 19"	15	0.18	1.1		2707	2708
2708	SS 2 RCEP S30 R19	SPAN 30", RISE 19"	15	0.18	1.2		2708	2709
2709	SS 2 RCEP S38 R24	SPAN 38", RISE 24"	284	0.18	72.7		2709	2710
2710	SS 2 RCP CL 3 15	DIA 15"	195	1.76	69.1		2711	2710
2711	SS 2 RCP CL 3 15	DIA 15"	196	1.75	76.4		2712	2711
2712	SS 2 RCP CL 3 15	DIA 15"	246	1.60	96.5		2713	2712
2713	SS 2 RCP CL 3 15	DIA 15"	241	1.60	61.5		2714	2713
2716	SS 2 RCEP S38 R24	SPAN 38", RISE 24"	62	0.30	26.8		4710	2716
2717	SS 2 RCEP S38 R24	SPAN 38", RISE 24"	294	0.25	-		2716	2800
2899	P CUL 1 RCCP 12	DIA 12"	37	0.27	-		2899	2900
4707	SS 1 RCP CL 4 15	DIA 15"	3	0.80	0.1		4707	2707
4708	SS 1 RCP CL 4 15	DIA 15"	3	0.80	0.1		4708	2708
4709	SS 1 RCP CL 4 15	DIA 15"	3	0.80	0.1		4709	2709
4710	SS 2 RCEP S38 R24	SPAN 38", RISE 24"	3	0.61	1.8		2710	4710
4711	SS 2 RCP CL 3 15	DIA 15"	3	1.00	1.4		4711	2711
4712	SS 2 RCP CL 3 15	DIA 15"	3	1.00	1.6		4712	2712
4713	SS 2 RCP CL 3 15	DIA 15"	3	1.00	1.4		4713	2713
4714	SS 2 RCP CL 3 15	DIA 15"	3	1.00	0.6		4714	2714

PIPE NO.	PIPE DESCRIPTION	PIPE SIZE	LENGTH (FT)	SLOPE (%)	TRENCH BACKFILL (CUYD)	SHEET NO.	FROM STRUCTURE	TO STRUCTURE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

DRAINAGE SCHEDULE
PROPOSED PIPES

SCALE:
DRAWN BY SN
DATE 07/05/06
CHECKED BY TKL

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

..\DU80A01.DGN, ..\DU80A01B.DGN, ..\DU80A02.DGN, ..\SDP99W08.DGN
6-28-2006,15:43:10 CARCIAAZ S:\DOCUMENT\02361501\CIVIL\DGN\DU80A011.SHT