

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 BY	WILL	505	232
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	DETL-232 OF 505	
CONTRACT NO. 60886				

SIGN REMOVAL SCHEDULE											
SIGN DESIGNATION	STATION	REMOVE SIGN PANEL		REMOVE SIGN PANEL TYPE (EACH)	REMOVE SIGN PANEL TYPE ASSEMBLY (EACH)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATION		REMOVE OVERHEAD SIGN STRUCTURE		
		SIZE (IN X IN)	AREA (SQ FT)				GROUND MOUNT (EACH)	OVER HEAD (EACH)	SPAN (EACH)	CANTILEVER (EACH)	BRIDGE MOUNTED (EACH)
D10-3	616+28 NB	12 X 48	4.00	1	A						
D10-3	616+34 SB	12 X 48	4.00	1	A						
GUIDE SIGN	619+60 SB	48 X 30	10.00	2	B						
M1-1	621+60 NB	48 X 48	16.00	2	B						
M3-1	621+60 NB	30 X 15	3.13	1							
NO PARKING	623+82 SB	18 X 24	3.00	1	A						
R2-4a	773+65 SB	48 X 96	32.00	3		1	1				
TOTAL											
REMOVE SIGN PANEL ASSEMBLY TYPE A					3						
REMOVE SIGN PANEL ASSEMBLY TYPE B					2						
REMOVE SIGN PANEL TYPE 3						32.00					
REMOVE GROUND MOUNTED SIGN SUPPORT							1				
REMOVE CONCRETE FOUNDATION - GROUND MOUNT								1			

NOTE:  
ALL SIGN PANELS SHALL HAVE  
WHITE LEGEND, GREEN REFLECTORIZED  
BACKGROUND UNLESS NOTED

**DAVID MASON & ASSOCIATES**  
Civil Engineering  
Structural Engineering  
Surveying  
410 E. Illinois, Suite 610  
Chicago, IL 60611  
(312) 942-9900

**PARSONS BRINCKERHOFF**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAL ROUTE 55  
US 30 (PLAINFIELD ROAD) TO LILY CACHE SLOUGH

SIGN PANEL DETAILS

SCALE: DRAWN BY: LC, JS, TC  
DATE: 06-30-06 CHECKED BY: SE