

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 55	**	WILL	505	396
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

\*\* SECTION 2006-032 BY  
CONTRACT NO. 60B86

SHEET NO. 2  
5 SHEETS

GENERAL NOTES:

- Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work; however, the Contractor will be paid for the quantity actually furnished at the unit price for the work.
- All Construction joints shall be bonded.

INDEX OF SHEETS

- Existing General Plan & Elevation
- General Notes & Bill of Materials
- Pier 1 Repair Details
- Pier 2 Repair Details
- Pier 3 Repair Details

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Concrete Removal	Cu. Yd.		0.5	0.5
Concrete Structures	Cu. Yd.		4.4	4.4
Reinforcement Bars, Epoxy Coated	Pound		310	310
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		178.3	178.3
Epoxy Crack Sealing	Foot		3	3

DESIGNED	S.CHELBIAN
CHECKED	J.GRAINAWI
DRAWN	D.C.PATEL
CHECKED	J.GRAINAWI

Date: 7/21/2006

GENERAL NOTES  
& BILL OF MATERIALS  
IL. ROUTE 126 (RAMP B)  
OVER FAI ROUTE 55 (I-55)  
SECTION 2006-032 BY  
WILL COUNTY  
STA. 1780+77.43  
STRUCTURE NO. 099-0031



7/25/2006 2:12:53 PM C:\16817A\Struc\Cadd\Pre-Final\US 126\Final Plans\02206-60B86-000-000-002.dgn