

SUMMARY OF QUANTITIES

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	588	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62303 • (2021-922 PT2 ETC 2324.6-1P) R-11				

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE								
				ROADWAY IDOT J000	ROADWAY CDOT J000	RETAINING WALLS		MWRD CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE
						69TH SW Y007	39TH-47TH Y007		Y002-1C	SFTY-3N	Y030-1E	Y032-1F
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	5	5								
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	764	764								
X0323907	COMMUNICATIONS VAULT	EACH	4									4
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	13,675	13,675								
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3,420	3,420								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	18,192	17,647		545						
X0324112	BARRIER BASE	FOOT	17,288	17,288								
X0324433	LIGHT TOWER, SERVICE PAD, 6"	SQ FT	136								136	
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	34,296			26,076	8,220					
X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2-4" DIA., CNC	FOOT	58									58
X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	499									499
X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA., CNC	FOOT	316								137	179
X0324472	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA., CNC	FOOT	258									258
X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA., CNC	FOOT	29									29
X0324697	SOIL STABILIZERS	POUND	1,695,770	1,695,770								
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	1,255	1,255								
X0324793	LIGHT TOWER, SERVICE PAD, SPECIAL	SQ FT	1,768								1,768	
X0325080	VIDEO TAPING OF MWRD CULVERT	FOOT	245					245				
X0325081	CONCRETE SLAB HYDRO-DEMOLITION	SQ YD	151					151				
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	11,443	10,921						522		
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	26,713	26,713								
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	3.2	3.2								
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	431	431								
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	288	288								
X4210400	LUG SYSTEM REMOVAL	EACH	2	2								
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	25,506	25,506								
X6061003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48 (MODIFIED)	FOOT	5,025	5,025								
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	283	283								
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	8,467	8,467								

• - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: 1"=N.T.S.
DATE: 06/09/06
DRAWN BY: RGR
CHECKED BY: DDM

Rev.

S00-07

6/9/2006 1:56:18 PM