

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*FAP 646 & FAP 638				
**=101BY-D & 137-1B-D				
***=WHITESIDE & HENRY				

BITUMINOUS CONCRETE SURFACE REMOVAL

IL	STAGE	SQ YD	LOCATION	COUNTY
IL 40		18.5	SN: 098-0015	WHITESIDE COUNTY
IL 82		5	SN: 037-0106	HENRY COUNTY
		<u>23.5</u>	TOTAL	

TEMPORARY PAVEMENT MARKING

IL	STAGE	WHITE	YELLOW	LOCATION	COUNTY
IL 40	STAGE I	920	920	624+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
IL 40	STAGE II	920	1840	624+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
		<u>1840</u>	<u>2760</u>	TOTAL	

WORK ZONE PAVEMENT MARKING REMOVAL

IL	STAGE	SQ FT	LOCATION	COUNTY
IL 40	STAGE I	306	624+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
IL 40	STAGE II	613	624+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
		<u>919</u>	TOTAL	

TEMPORARY CONCRETE BARRIER

IL	STAGE	FOOT	LOCATION	COUNTY
IL 40	STAGE I	120	632+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
		<u>120</u>	TOTAL	

RELOCATE TEMPORARY CONCRETE BARRIER

IL	STAGE	FOOT	LOCATION	COUNTY
IL 40	STAGE II	120	632+ 22.5 - 633+ 42.5	WHITESIDE COUNTY
		<u>120</u>	TOTAL	

PAINT PAVEMENT MARKING LINE 4"

IL	STAGE	WHITE	YELLOW	LOCATION	COUNTY
IL 40		3680		624+ 22.5 - 633+ 42.5	WHITE EDGELINES - 2 COATS
IL 40		920		624+ 22.5 - 633+ 42.5	SKIP DASH WHITE - 2 COATS
IL 82			108	636+ 2.5 - 636+ 45.5	SOLID RT/SKP DASH LEFT
IL 82		172		636+ 2.5 - 636+ 45.5	WHITE EDGELINES - 2 COATS
		<u>4772</u>	<u>108</u>	<u>4880</u>	TOTAL

PAINT PAVEMENT MARKING REMOVAL

IL	STAGE	FOOT	LOCATION	COUNTY
IL 40		920	624+ 22.5 - 633+ 42.5	
		<u>920</u>	TOTAL	

TEMPORARY PAVEMENT

IL	STAGE	FOOT	LOCATION	COUNTY
IL 40		72	SN: 098-0015	WHITESIDE COUNTY
IL 82		28	SN: 037-0106	HENRY COUNTY
		<u>100</u>	TOTAL	

TEMPORARY PAVEMENT REMOVAL

IL	STAGE	FOOT	LOCATION	COUNTY
IL 40		72	SN: 098-0015	WHITESIDE COUNTY
IL 82		28	SN: 037-0106	HENRY COUNTY
		<u>100</u>	TOTAL	

IMPACT ATTENUATORS, TEMPORARY (NON-DIRECTIVE), TEST LEVEL 3

IL	STAGE	EACH	LOCATION	COUNTY
IL 40	STAGE I	1	632+ 22.5 OUTSIDE LANE	WHITESIDE COUNTY
IL 40	STAGE II	1	632+ 22.5 INSIDE LANE	WHITESIDE COUNTY
		<u>2</u>	TOTAL	

IMPACT ATTENUATORS, RELOCATE (NON-DIRECTIVE), TEST LEVEL 3

IL	STAGE	EACH	LOCATION	COUNTY
IL 40	STAGE I	1	632+ 22.5 OUTSIDE LANE	WHITESIDE COUNTY
IL 40	STAGE II	1	632+ 22.5 INSIDE LANE	WHITESIDE COUNTY
		<u>2</u>	TOTAL	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. DATE  
HORIZ. DATE

DRAWN BY  
CHECKED BY

PLOT DATE = Fri Jul 14 08:06:55 2006  
 FILE NAME = c:\p\m\m\m\211696\dl1696.dgn  
 PLOT SCALE = 3/8"=1'-0"  
 USER NAME = gpfj