CONTRACT NO. 66649

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-1VB)I-3	LASALLE	16	3
FED. ROAD DIST. NO. _	ILLINOIS	NON-FED. AID PROJECT		

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	248
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	19
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	44
42001300	PROTECTIVE COAT	SQ YD	339
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	275
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	54
44000700	APPROACH SLAB REMOVAL	SQ YD	192
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	87
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5
50102400	CONCRETE REMOVAL	CU YD	11.2
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	86
50300225	CONCRETE STRUCTURES	CU YD	13.2
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1520
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2080
60101805	PIPE DRAINS, 8" (SPECIAL)	FOOT	90

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. ROUTE 39 OVER NORFOLK SOUTHERN RAILROAD

F.A.I ROUTE 39 SECTION: (50-1VB)I-3

LASALLE COUNTY

STA. 565+86.08

Date: 05/09/2006
File: c:/proj/acts/cms1n07/cm303/defails.dgn