

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	10IRS-6	MONTGOMERY	16	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 72816

**PAVEMENT MARKING**

STATION	TO	STATION	SHORT TERM PAVEMENT MARKING FOOT	TEMPORARY PAVEMENT MARKING LINE 5" FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	PAINT PAVEMENT MARKING LINE 5" FOOT	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL EACH
830+07	TO	953+00	3,324.0	27,666.0	1,385.0	27,666.0	155	155
953+00	TO	962+92	276.0	2,233.9	115.0	2,233.9	13	13
962+86	TO	965+67	84.0	642.1	35.0	642.1	5	5
908+80	TO	925+20		1,640.0		1,640.0		
PROJECT TOTAL			3,684.0	32,182.0	1,535.0	32,182.0	173	173

**TEMPORARY RAMP**

STATION	BITUMINOUS SURFACE REM-BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD
830+07.00	140.00	15.60
916+75.00		8.90
917+25.00		8.90
831+75.00	21.80	
832+90.00	31.10	
841+85.00	43.30	18.90
855+79.00	43.30	18.90
908+17.00	43.30	18.90
908+17.00	43.30	18.90
933+00.00	19.40	
935+72.00	43.30	18.90
942+75.00	28.80	
951+50.00	42.20	
956+55.00	76.70	33.90
957+65.00	27.60	
958+24.00	9.70	
962+00.00	54.40	18.90
965+67.00	140.00	15.60
PROJECT TOTAL	808.0	196.0

**PAVEMENT**

BEGINNING STATION	ENDING STATION	BITUMINOUS MATERIALS (PRIME COAT) TON	AGGREGATE (PRIME COAT) TON	AGGREGATE SHOULDERS, TYPE B TON	POLYMERIZED BIT CONC SURFACE COURSE SUPERPAVE, MIX "D", N70, 1 1/2" TON	INCIDENTAL BITUMINOUS SURFACING SUPERPAVE, N50 TON	PREPARATION OF BASE SQ YD
830+07.00	953+00.00	29.07	76.49	1050.00	3211.18		
953+00.00	962+91.93	2.35	6.17	84.70	259.22		
962+85.96	965+67.00	0.66	1.75	24.00	73.45		
908+80.00	912+00.00	0.18	0.46		19.41		
912+00.00	916+75.00	0.52	1.37		57.63		
917+25.00	922+00.00	0.52	1.37		57.63		
922+00.00	925+20.00	0.18	0.46		19.41		
831+75	RT	0.01	0.07	-1.50		2.70	21.8
832+90	LT	0.02	0.10	-2.00		3.90	31.1
841+85	RT	0.03	0.14	-2.10		5.50	43.3
855+79	LT	0.03	0.14	-2.10		5.50	43.3
908+17	LT	0.03	0.14	-2.10		5.50	43.3
908+17	RT	0.03	0.14	-2.10		5.50	43.3
933+00	LT	0.01	0.06	-1.40		2.50	19.4
935+72	RT	0.03	0.14	-2.10		5.50	43.3
942+75	LT	0.02	0.09	-1.90		3.60	28.8
951+50	RT	0.03	0.13	-2.10		5.30	42.2
956+55	LT	0.05	0.25	-3.60		34.30	76.7
957+65	RT	0.02	0.09	-2.00		5.40	27.6
958+24	LT	0.01	0.03	-1.50		1.90	9.7
962+00	RT	0.03	0.17	-2.50		6.90	54.4
962+00	LT	0.01	0.03			8.10	
PROJECT TOTAL		35.0	90.0	1,130.0	3,698.0	103.0	528.0

**SURFACE REMOVAL**

BEGINNING STATION	ENDING STATION	BITUMINOUS SURFACE REM (VAR DEPTH) SQ YD	PAVEMENT REMOVAL SQ YD
830+52.00	916+45.00	26,733.8	
916+45.00	917+55.00	342.2	
917+55.00	953+00.00	11,028.9	
953+00.00	962+91.93	3,086.0	
962+85.96	965+22.00	734.4	
908+80.00	912+00.00	231.1	
912+00.00	916+75.00	686.1	
917+25.00	922+00.00	686.1	
922+00.00	925+20.00	231.1	
961+70.00	962+30.00		25.0
PROJECT TOTAL		43,759.0	25.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAP ROUTE 42 (IL 48 / IL 127)  
 SECTION 10IRS-6  
 MONTGOMERY COUNTY

**SCHEDULE OF QUANTITIES**

DRAWN BY: DLB

CHECKED BY: CAS

**SCHEDULE OF QUANTITIES**