

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	10IRS-6	MONTGOMERY	16	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 72816

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH @ EOP	WIDTH @ LENGTH OF IMPROVEMENT	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONC THICKNESS	BIT. SURF. REM. - BUTT JOINT	PREP OF BASE	BIT MATERIALS PRIME COAT	AGG PRIME COAT	INCIDENTAL BIT. SURF. SUPERPAVE N50	TEMP RAMP	REMARKS
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH/AGG/BIT P.C.C. / CL A2 SURF)	FOOT	FOOT	FOOT	INCH	SQ. YD.	SO. YD.	TON	TON	TON	SO. YD	
RT STA 831+75	PE	BIT	35	21	7	2.25	21.8	21.8	0.01	0.07	2.7		
LT STA 832+90	PE	BIT	47	33	7	2.25	31.1	31.1	0.02	0.10	3.9		
RT STA 841+85	SALE CIRCLE DRIVE	BIT	49	29	10	2.25	43.3	43.3	0.03	0.14	5.5	18.9	
LT STA 855+79	EAST 4TH ROAD	BIT	49	29	10	2.25	43.3	43.3	0.03	0.14	5.5	18.9	
LT STA 908+17	EAST 5TH ROAD	BIT	49	29	10	2.25	43.3	43.3	0.03	0.14	5.5	18.9	
RT STA 908+17	EAST 5TH ROAD	BIT	49	29	10	2.25	43.3	43.3	0.03	0.14	5.5	18.9	
LT STA 933+00	PE	BIT	32	18	7	2.25	19.4	19.4	0.01	0.06	2.5		
RT STA 935+72	SALE CIRCLE DRIVE	BIT	49	29	10	2.25	43.3	43.3	0.03	0.14	5.5	18.9	
LT STA 942+75	PE	BIT	44	30	7	2.25	28.8	28.8	0.02	0.09	3.6		HENDERSON LANE
RT STA 951+50	CE	BIT	49	27	10	2.25	42.2	42.2	0.03	0.13	5.3		BLESSED HOPE BAPTIST CHURCH
LT STA 956+55	GREENBRIAR DRIVE	CL A2 SURF	85	53	10	8	76.7	76.7	0.05	0.25	34.3	33.9	
RT STA 957+65	PE	AGG	47	24	7	3.5	27.6	27.6	0.02	0.09	5.4		CLAYTON DRIVE
LT STA 958+24	MB	BIT	36	22	3	3.5	9.7	9.7	0.01	0.03	1.9		
RT STA 962+00	DORSELL ROAD	BIT	59	39	10	2.25	54.4	54.4	0.03	0.17	6.9	18.9	
SCHEDULE TOTAL =							528.2	528.2	0.35	1.69	94.0	147.3	

SHEET 3 OF 3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 42 (IL 48 / IL 127)
 SECTION 10IRS-6
 MONTGOMERY COUNTY
ENTRANCE IMPROVEMENT SCHEDULE
 SCALE: _____ DRAWN BY DLB
 DATE _____ CHECKED BY CAS

ENT PPP