

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2647	99-00142-07-WR	LAKE	256	150
CONTRACT NO: 83815				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				



48" x 36"
 WHITE ON GREEN
 REFLECTIVE BACKGROUND
 1" BORDER WITH 5/8" INSET
 LETTER SIZE 6C



48" X 36"
 BLACK ON FLUORESCENT ORANGE
 REFLECTIVE BACKGROUND
 1" BORDER WITH 5/8" INSET
 LETTER SIZE 6D
 *LETTER SIZE 6E BOLD

NOTE: ALL ENTRANCE SIGNS TO BE PLACED BY COUNTY FORCES.

TEMPORARY CONSTRUCTION INFORMATION SIGNING NOTES:

1. The entrance signs shall be mounted back to back on the near right side of the roadway where the entrance is located and the arrow on the entrance sign shall indicate the side of the roadway where the entrance is located.
2. Temporary construction information signs shall be post mounted 7' (2.1 m) above the near edge of pavement and shall be a minimum of 6' (1.8 m) beyond the edge of the nearest traveled lane, or as directed by the engineer.
3. The retroreflective sign face shall be a minimum of type "A" material.
4. The temporary construction information signs shall be removed or relocated when the engineer determines the signs to be no longer necessary.
5. Existing traffic control signs and messages that are in conflict with the proposed maintenance of traffic shall be covered or modified with temporary overlay as shown in the plans and/or as directed by the engineer.
6. Install additional temporary sign panel assemblies as shown in the plans and/or directed by the engineer.



APPROVED BY: ANK
 DATE: 01/09/03

TEMPORARY CONSTRUCTION
 INFORMATION SIGNS

LC7007

REVISIONS	DATE
NEW SIGNS, NEW TEXT	01/09/03

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU 2647 - BUTTERFIELD ROAD
TEMPORARY CONSTRUCTION INFORMATION SIGNS

SCALE: NONE
 DATE: 12/2/2005

DRAWN BY: N/A
 CHECKED BY: N/A